SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LI.—No. 24. [NEW SERIES.] NEW YORK, DECEMBER 13, 1884. [$3.20 per Annum. [POSTAGE PREPAID.]

THE MAXIM MACHINE GUN.

The mitrailleuse, or machine gun, as hitherto constructed, is a weapon in which all the functions of loading, cocking, firing, and extracting the empty shell from the gun are performed by turning a crank or by working a lever. The first successful gun of this kind was the invention of Dr. Gatling, an American. This gun was brought out during the war of the rebellion, and before metallic cartridges, which are so essential to the success of a machine gun, had reached their present degree of perfection.

Dr. Gatling did not succeed in getting his gun used to any extent in the war of 1860–64. The first machine gun which ever saw service in the field was the French mitrailleuse. This gun was large, absurd, and clumsy, and so heavy that it required to be drawn by horses; it would fire but 150 shots per minute. It did not comprise the necessary elements of success, and consequently failed.

The next machine guns to make their appearance were the Hotchkiss, the Lowell, the Nordenfelt, and the Gardner. All of these, except the Nordenfelt, were operated by a hand crank, the Nordenfelt alone being actuated by a reciprocating lever. All of these guns must necessarily be mounted upon a firm base, and be trained and elevated by screws and worm gears. If they were made to work freely upon a pivot or universal joint, they would not be firm enough to remain stationary while the crank or handle was being operated. The safe speed at which a machine gun can be fired depends in a great measure upon the kind and age of cartridges used. For instance, if cartridges have been made for some time, a trifling amount of moisture may have accumulated in the powder near the primer. When this dampness occurs, the cartridges are said to hang fire, that is, they do not explode at the instant of being struck. Suppose that one cartridge in a thousand should hang fire; it would be necessary to operate the gun sufficiently slowly on the entire series to give this slow cartridge time to explode, otherwise it might be drawn from the barrel before it exploded, or in the act of exploding, in either of which cases it would disable the gun. To this may be attributed a great deal of the trouble in operating machine guns, and their liability to get out of order when most needed. In the gun of which we publish illustrations herewith and which is the invention of Mr. Hiram S. Maxim, of Hatton Garden, London, slow cartridges do not offer an obstacle to the rapid firing of those which will explode quickly, from the fact that no cartridge can be drawn from the gun until it has exploded, as it requires the force of its own explosion to unlock the block from the barrel and extract the empty shell. In Mr. Maxim's new gun there is but one barrel, and all the functions of loading, cocking, firing, withdrawing the empty shell from the barrel, and ejecting it, are performed by the recoil resulting from the explosion. This gun may be likened to a small engine, the barrel under the influence of the recoil acting as the piston, the block as the crosshead, and the sear and trigger as the valve gear. The cartridges to the number of 333 are placed side by side in a canvas belt, secured together with brass eyelets and strips. One end of this belt is connected to the arm, and the gun is operated by hand until the first cartridge is driven into the barrel. Then the trigger is pulled, this cartridge explodes, the breech bolt is unlocked from the barrel, the empty case is extracted, moved to one side, a loaded cartridge is brought in front of the barrel, the arm is cocked, the cartridge pushed home, and the trigger pulled, when the explosion of the second cartridge operates the same as the first. Thus the firing may be kept up automatically without any action on the part of the attendant as long as there are any cartridges in the belt. Our engravings represent respectively a side view and a front view of the gun and its stand, a longitudinal section of the barrel and the mechanism, and a detail of the firing device. The weapon is mounted upon a tripod stand (Figs. 1 and 2), and between it and the top of the stand there is placed a magazine, which is protected from the enemy's fire by a pair of light shields. The gun can be rotated about the vertical axis by means of a handle (Fig. 1) which turns a tangent screw; or if the three-armed nut at the bottom of the axis be slackened, the barrel can be moved by hand to spread the fire over a considerable area. If a definite piece of ground is to be subject to the fire, such as a bridge, a pass, or a ford, the gun can be sighted in succession to each end of the space and its motion beyond those limits prevented by adjustable nuts on the screw spindle. The elevation of the barrel is altered by turning the hand wheel on the strut, stretching from the stand to the rear of the gun. By slackening a clip on this strut the screw is thrown free, and the weapon can be elevated and depressed.

We will now consider the mechanism by which the loading and firing is effected. The barrel, B, which is inclosed in a water jacket (Fig. 5), is capable of a longitudinal motion of about seven-sixteenths of an inch upon the explosion of a cartridge, and moves back, pushing before it the breech bolt, the sear, and the rest of the moving parts. Its motion is in the first instance opposed by two springs, which are forced outward by the toggle arms. As soon as the arms have passed the center, the springs begin to close again, and aid the motion of the barrel. At first, as we have already said, the barrel and the block or breech piece, A, travel back at the same speed, but for the spent shell to be extracted and the new cartridge to take its place, the block, A, must leave the barrel a considerable distance for the other mechanism to come into play.

The two are at first fixed together by the locking latch, C, which is held down by the stop, N. A slight

Continued on p. 398.



Fig. 1.—THE MAXIM SELF-ACTING MACHINE GUN.



Fig. 2.

© 1884 SCIENTIFIC AMERICAN, INC



Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN. A. E. BEACH.

TERMS FOR THE SCIENTIFIC AMERICAN.

One copy, one year postage included..... **$3 20**
One copy, six months postage included..... **1 60**

Clubs.—One extra copy of THE SCIENTIFIC AMERICAN will be supplied gratis for every club of five subscribers at $3.20 each; additional copies at same proportionate rate. Postage prepaid.

Remit by postal order. Address

MUNN & CO., 361 Broadway, corner of Franklin street, New York.

The Scientific American Supplement

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, $5.00 a year, postage paid, to subscribers. Single copies, 10 cents. Sold by all newsdealers throughout the country.

Combined Rates.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year postage free, on receipt of *seven dollars*. Both papers to one address or different addresses as desired.

The safest way to remit is by draft, postal order, or registered letter. Address MUNN & CO., 361 Broadway, corner of Franklin street, New York.

Scientific American Export Edition.

The SCIENTIFIC AMERICAN Export Edition is a large and splendid periodical, issued once a month. Each number contains about one hundred large quarto pages, profusely illustrated, embracing: (1.) Most of the plates and pages of the four preceding weekly issues of the SCIENTIFIC AMERICAN, with its splendid engravings and valuable information; (2.) Commercial, trade, and manufacturing announcements of leading houses. Terms for Export Edition, $5.00 a year, sent prepaid to any part of the world. Single copies 50 cents. ☞ Manufacturers and others who desire to secure foreign trade may have large, and handsomely displayed announcements published in this edition at a very moderate cost.

The SCIENTIFIC AMERICAN Export Edition has a large guaranteed circulation in all commercial places throughout the world. Address MUNN & CO., 361 Broadway, corner of Franklin street, New York

NEW YORK, SATURDAY, DECEMBER 13, 1884.

Contents.

(Illustrated articles are marked with an asterisk.)

Ardea cœrulea... 399
Bell telephone patents sustained, the..... 393
Belt material 392
Business and personal..... 402
Camera lucida, new 391
Car, refrigerating, Tallichet's*.. 395
Cattle, fine specimens of*..... 399
Cattle, the slaughtering of..... 393
Cheese, poisonous 401
Cider, how to keep sweet..... 396
Civil service reform in mines... 396
Congress and Patent Office..... 393
Criminal ignorance..... 392
Drawers, Towle's*..... 396
Florida woman, a, who runs a sawmill 400
Gold leaf 392
Gun, machine, self-acting*..... 391
Heaters, acetate of soda..... 397
Ink, indelible, stamping 397
Inventions, agricultural..... 402
Inventions, engineering 402
Inventions, miscellaneous..... 402
Inventors, American, more time for 393
Inventors, treatment of, shameful 396
Lantern, electrical, new..... 398
Madagascar..... 393
Metal, basic, a..... 393
Mica sheet, composite*..... 396
New books and publications..... 402
Notes and queries..... 402, 403
Pens, steel, how made..... 401
Photographs, magic..... 396
Pulleys and gears..... 392
Putnam River, Alaska..... 396
Steel hardened by pressure..... 401
Suggestion to employers..... 396
Superheating as a cause of boiler explosions, experiments on*. 394
Telegraph line, pneumatic, at Paris*..... 395
Tree, bird catching..... 400
Water, sea, artificial, for aquaria 400
Weather, to foretell 393
Worms, earth..... 397

TABLE OF CONTENTS OF

THE SCIENTIFIC AMERICAN SUPPLEMENT

No. 467,

For the Week ending December 13, 1884.

Price 10 cents. For sale by all newsdealers.

PAGE

I. CHEMISTRY AND METALLURGY.—Determination of Tannin.—By E. JOHANSON..... 7458
The Incomplete Combustion of Gases.—By H. B. DIXON.—Abstract of paper read before the British Association at Montreal.... 7453
Aluminum and its Alloys..... 7462

II. ENGINEERING AND MECHANICS.—The New Dam at Suresnes.—With engraving..... 7453
Brearey's Aeronautical Machine.—With engraving..... 7453
Raising of the Fallen Girders of the Douarnenez Viaduct.—2 engravings 7454
Improved Wire Testing Machine.—With engraving..... 7454
Improved Doubling and Laying Machine.—With engraving..... 7454
Boiler Tubes..... 7455
Improved Ladle Carriage.—2 figures..... 7455
The Repair of Boiler Tubes.—11 figures..... 7455
Grulet's Screw for Raising Water.—1 engraving..... 7456

III. TECHNOLOGY.—On Various Toning Baths.—Several experiments.—By W. M. ASHMAN..... 7456
Coating Plates with Gelatine Emulsion.—6 figures 7457
Iodo-chloride of Silver Emulsion.—By V. SCHUMANN..... 7458
Apparatus for Saturating Water with Sulphurous Acid.—1 engraving..... 7458

IV. PHYSICS, ELECTRICITY, ETC.—The Wave Theory of Light.—By SIR WM. THOMSON.—Sound and light due to wave vibrations.—Difference between vibrations of light and sound.—Radiant heat.—Solar spectrum.—Luminiferous ether.—How to measure wave lengths of light and the frequency of vibrations.—With diagrams. 7448
The Limitations of Submarine Telegraphy 7450
Williams' System of Coast Defense by Electrical Torpedoes.—Full page of figures..... 7451
New Electric Gas Lighter.—2 figures..... 7452
Insulators for Telegraph and Telephone Lines.—9 figures..... 7452
Electric Light in Theaters 7452
Rings of Smoke.—5 figures..... 7461

V. ARCHITECTURE.—The New Technical High School at Berlin.—With engraving..... 7447
The New University Buildings at Strassburg.—2 engravings..... 7447

VI. BOTANY, ETC.—An Improved Hyacinth Glass..... 7461
The Botanical Club of the American Association..... 7461

VII. HYGIENE, MEDICINE, ETC.—Herbst's Method of Filling Teeth.—Demonstrated by Dr. G. C. CLUDINS..... 7459
Dr. Koch's Berlin Lecture on Cholera and the Comma Bacillus.. 7459
Local Anæsthesia by the Hydrochlorate of Cocaine.—By R. J. LEWIS, M.D..... 7459
On Sewage Disposal on Land, by Chemical Treatment, and by Discharge into River or Sea.—By Prof. H. ROBINSON..... 7460

VIII. MISCELLANEOUS.—The New York Street Cars.. 7460
Petroleum Wells..... 7462

BELT MATERIAL.

The first idea of a belt for machine purposes is a leather band, but other materials have been used for many years; the writer remembers seeing a six inch or an eight inch belt that had run for more than a year in a wood working establishment, which was made of cotton cloth—sail duck. The belt connected two pulleys of three feet and two feet diameter respectively, the shafts of which were on the same level. To compensate for the shortening and lengthening of the belt by the changes in humidity of the atmosphere, a pivoted idler was used. This change of length appeared to be the only serious drawback to the employment of cotton as belt material; for the adhesion of the material to the face of the pulley was excellent.

Rubber belting is simply cloth and rubber united by being pressed between heavy rollers; its strength depends on the fibrous portion—the cloth. There has recently been another cloth belt put upon the market, that depends for its adhesiveness to the pulley face on cotton. This a woven belt, the woof or warp of which is of a series of continuous steel wires, the filling being coarse cotton yarn or twine. No preparation is given the cotton, either before or after the weaving, and the "shed" in weaving is so arranged that the steel wires, on which the strength of the belt depends, are entirely covered. One of these belts has been noticed by the writer for more than two years—a twelve inch belt leading from the fly wheel of an engine—and it shows no sign of destructive wear yet, and has absolutely no stretch. From these examples it would appear that under some circumstances (those of a dry atmosphere, equable temperature, and an unshipable belt), cotton might prove to be an excellent substitute for leather for belting purposes.

There appears to be only one sort of leather that is properly applicable to belt making—that from the skin of the ox or *Bos* tribe. During a residence of several years in one of the British American provinces, the writer was compelled by circumstances to make his own belts, of such material as could be obtained. Moose hide leather was tried, but it had a quality of indefinite stretch; to obtain a six inch wide belt, strips not less than ten inches wide were required, and these were wetted and stretched by powerful winches for several days before they were fit to cut to width. The leather was very thin for the width of belt, but it was wonderfully tenacious and adhesive. Raw hide (untanned skin) will do fairly well as a belt if kept soft by oil, but it lacks the hug of leather, and has little elasticity.

Ox leather belts stand at the head of those of all other materials for the satisfaction of all demands on belts. No other belts will stand the wear of the shipper; cotton belts are weakened when wet; rubber belts are rotted when oiled, but leather will stand wet and dryness, cold and heat, and lasts a long time even when oil saturated.

GOLD LEAF.

If a sheet of gold leaf is held up against the light, it appears to be of a vivid dark green color; this means that the light is transmitted through the leaf. When it is considered that this leaf is a piece of solid metal, a better idea of the extreme tenuity of thickness of the leaf can be comprehended than by any comparison by figures; nothing made by the hand of man equals it in thinness. This extreme thinness is produced by patient hammering, the hammers weighing from seven to twenty pounds, the lighter hammers being first used. When the true method of this beating is understood, the wonder expressed sometimes that gold leaf beating should not be relegated to machinery ceases; the art belongs to the highest department of human skill and judgment. Apprentices have served a term, and have been compelled to abandon the business, because they never could acquire the requisite skill and judgment combined necessary to become successful workmen.

The only pure gold leaf is that used by dentists for filling carious teeth, and it is called foil. It is left much thicker than the gold leaf for gilding—indeed, it could not be beaten so thin; for thin or leaf gold an alloy of silver and copper is required to impart the requisite tenacity. Dentist's foil weighs six grains, five, four, and three grains per sheet, or leaf, according to its thickness. The last operation on the leaf is annealing. This is done over a charcoal fire, the leaf being laid singly in a sort of corn popper—a square receptacle with wire bottom at the end of a handle—over which is held a similar cover to prevent the flame from carrying the leaf away. An instant's exposure to the flame induces a red heat, when the leaf is laid on a sheet of a book.

The material for gold leaf and dentist's foil is coin gold. The gold is precipitated by muriatic and nitric acids over a fire to separate the gold and silver, the copper of the alloy passing off in the heat. The silver from gold coin amounts to about seven pennyweights to $800 worth of coin—the amount usually treated at a time. This reduction and separation of the metals is the usual method, and does not require special description.

The pure gold is then melted in sand crucibles with the proper proportions of silver and copper to produce the color of leaf desired, very fine ornamental effects being produced in gilding with leaf of differing shades. The fluid metal is poured into iron moulds, making bars seven inches long, one and an eighth inches wide, and one-fourth of an inch thick. These bars are forged, like iron, between anvil and hammer, to even the edges, and then rolled in powerfully geared rolls to a ribbon not thicker than writing paper and one inch wide. Of course, in the rolling as in all the processes, there must be occasional annealings.

Now comes the first of the beating processes. These squares of gold (one inch square) are placed in a pile alternating with larger squares (four inches or more) of "kutch" paper, a material made from a pulp of animal membrane—raw hide, intestines, etc.—and the outside of the pile receives a square of parchment. The hammering then begins with a seven pound hammer on a block of marble that rests on a solid foundation. After one hour's beating the pile is warmed at a fire to anneal the gold, a process requiring care, so that the kutch paper be not burned. Four hours of beating suffices for this preliminary process, 180 squares of gold being treated in one pile. The final process requires great skill. The partially beaten squares are packed as before, but with alternates of gold beater's skin, until the pile contains 900 sheets. The beating is continued with increasingly heavier hammers until the final finish with the twenty pound hammer. The gold beater's skin comes from England, and the best of it—and the most of it—is made by one family—Frederick Perkins. The skin is so thin as to be almost transparent, and yet it is double, two thicknesses. It is prepared from the larger intestine of the ox. Each sheet of the skin is rubbed on each side, before the pack is made and whenever the pack is rearranged (placing the outer gold in the center and *vice versa*), with a powder made from calcined gypsum of a very pure sort, imported from Germany. This is to prevent the gold from sticking to the skin.

In beating, the work of spreading the gold is from the center of each square of gold out toward the edges, and the finished squares are thicker at the edges than in the center. A contrary spreading would split the edges and ruin the squares. In rearranging the squares in the process of beating they are sometimes torn, but another piece laid on as a patch, lapping over the torn place, will be firmly welded in the after beating.

The finished squares are cut to a size of three and three-eighths inches, and packed in a "book" holding twenty-five sheets, the paper leaves being rubbed with red ocher to prevent sticking. These books of twenty-five sheets are sold at from thirty to forty cents each. The cutting of the leaf is done by knives, which are simply slips of the outer shiny shell or skin of the Malacca cane such as is used for walking sticks. The outer rind contains silex or flint in minute, invisible particles, forming a peculiar edge. Steel will not answer the purpose.

CRIMINAL IGNORANCE.

The October number of *The Locomotive* has an editorial article on the foolish carelessness of engineers of stationary engines that ought to be generally read, because it tells the truth where subterfuge and pretense has sometimes blinded judgment. Engineers are not, as a class, pretenders and cheats; but there are many who pretend to know their business who are simply and only swindlers; who do not know the manual of their business even, and never thought of knowing its chemical and mechanical reality.

The Locomotive says:

The carelessness sometimes displayed by engineers (?) who have charge of boilers is simply criminal, and deserves the severest penalties. A recent occurrence will illustrate this. Visiting an establishment where we had boilers insured, our attention was attracted by the suspicious actions of the engineer. Watching for what he supposed was a favorable opportunity, he climbed up on top of the boilers and headed toward the safety valve, always keeping as nearly between it and us as he could, but not, however, succeeding in always keeping from view. Reaching the valve he busied himself a few moments about it, and then returned with a nonchalant air to where we were. The following conversation then occurred:

Inspector: "Tired of living, are you?"
Engineer: "No; what do you mean?"
Inspector: "I thought perhaps you were."
Engineer: "What makes you think so?"
Inspector: "Why, from the use you make of that wedge you now have in your overalls pocket. I see that you had the safety valve fastened down with it. Now, if you want to die, why don't you go out and jump into the river, and drown yourself; then nobody's life but your own would be endangered?"
Engineer: "Those boilers are all right. I don't believe a boiler can blow up so long as there is plenty of water in it. I have been running boilers twenty years." And so on to the end of the chapter.

This fellow had actually made an iron wedge, and driven it into the forked guide above the lever, so that it was impossible for the valve to lift, in order to "bottle up the steam," as he expressed it. And this in spite of the fact that the pressure was all that could be safely allowed; and he had also moved the weight out on the lever fifteen pounds beyond the limit allowed. This is an actual occurrence.

PULLEYS AND GEARS.

In American practice, pulleys have led gears for more than thirty years. There was a time when no large establishment driven by power could be arranged to run except by gearing; all the main shafting was geared to the prime mover, and if that was a steam engine a jack wheel instead of a belt imparted motion from the fly wheel or crank shaft. The writer remembers a set of cards in a cotton mill; the cylinders, licker-ins, doffers, and even the doffer combs, were all connected by gear wheels. Years after the grinding, wearing, noisy main gears were superseded here by the smoothly running pulleys and belts, the English adhered to the toothed wheel system. It had its value; it has its advantages, and the gear wheel is taking its place as a valuable adjunct to machinery of all kinds. One of these advantages is its absolute security; "give a tooth take a tooth" is an old adage in mechanics, and is an absolute law in gear-

© 1884 SCIENTIFIC AMERICAN, INC

ing; there is no slipping and no failure of transmission of power.

But there were objections to the gear, and although some have been removed, others remain. One of the great objections to the gear, as it was formerly made, was its tendency to crowd apart—the two gears working against each other rather than with one another. But with the recent improvements in gear teeth cutting that objection is entirely removed; gears properly cut run together with no inclination whatever to come apart, except with a speed that develops centrifugal force. Some recent experiments seem to prove that the forcing apart tendency of well cut gears is reduced to *nil;* while on the other hand the connection of pulleys by belts necessitates a very strong pulling together, proportioned to the diameter of pulleys, width of belts, distances apart of the pulleys, and their relative positions.

Another objection to the use of gears is where the reach is considerable between the shafts; in which case the only connection feasible is by means of one or two intermediates, as the direction of revolution may demand. If the two connected shafts are to revolve in the same direction, a single intermediate may be used; but it is evident that the diameter of this wheel must be sufficient to reach between the peripheries of the two other wheels, else three intermediates must be employed. Sometimes these transmitters—or otherwise idlers—are unhandy, and then the advantage of pulleys and belts is apparent. The belt and pulley have a reach that is impossible without a train of gearing or a belt connection of links of machine chain. Except for this lack of reach it is evident that the gear connection is superior in itself to the pulleys and belt, which at its best must be considered a makeshift for an absolute transmitter.

A BASIC METAL.

The title of "the iron age," which has been applied by some writers to the present period, seems to demand some modification or addition; copper has become fashionable in our houses, in our public buildings, and in our monuments. It appears pure, or in alloys forming bronzes and brasses of a variety of color and a number of degrees of tenacity, obduracy, and durability. This is a revival of the fashions of several generations ago. It is a good one, however, for there is a limit to the tractability of iron and steel, and the eye tires of non-colored metal as it would of neutral tinted clothing.

The capacity of copper for combining with others forming different alloys is not possessed so fully by any other metal; with zinc the brasses that may be made vary from the deep red of the copper itself to the gray white of the zinc, and in tenacity from that of the toughest, purest copper to the hard brittleness of spelter. In combination with tin its products are still more varied in color and perfect in beauty.

Not one of the alloys of copper is subject to destructive oxidation when exposed to air, water, or steam; but by weather exposure the beauty of the bronzes is enhanced and their durability insured. There is more brass used in the machine shop than formerly; the work of the machinist of today is not limited to iron and steel; he must know the qualities of the "composition" he is working and how to work it well. Brass finishing can hardly be called a distinct trade nowadays. Recently there was noticed in a large machine manufacturing establishment one of its products that consisted of three-fourths by weight of copper and its compounds and only one-fourth of iron and steel. The work was of such a character as required the skill and tools of the machinist and the conveniences of the machine shop. Said the superintendent, a machinist of more than thirty years' experience:

"I can tackle any job now. Time was when I would have sent copper and brass work to the coppersmith and the brass finisher, but we must do these mixed jobs if we would do any work. So I compelled myself to learn the working of these metals, and then I taught my men. A machinist who can't work copper, bronze, and brass is not a competent workman."

The value of copper compositions in machinery is very great; a casting of bronze or of brass is wholly unlike one of iron in its tenacity, and it may combine this sometimes necessary quality with a hardness (durability under wear) that no iron casting can possess. These combined qualities cannot be imitated by any other metal. The writer once successfully proved this advantage. A small pinion made first of cast iron, then of cast steel, and lastly of forged Lowmoor iron, broke, or stretched beyond usefulness, when one of tough bronze was tested with satisfactory results.

To Foretell Weather.

Weather wise prognosticators seem to be on the increase. In last week's issue we quoted from a Cincinnati observer his method of foretelling the changes in the weather, from watching the habits of animals; and there now comes from the South a weather prophet who adds a long list of the signs which he has observed to precede changes in the weather.

Few intelligent persons, says the *Southern Planter,* can have any sympathy with the so-called prophets who oracularly announce phenomena, giving dates, occasionally making lucky hits, but as often firing their random shots altogether wide of the mark. That there is, however, something in weather philosophy, intelligent persons will be quite ready to concede, and they will be in accord with the view of the writer when he recommends the observation of natural phenomena, which has been long practiced. He says:

If one could read the signs, each day foretells the next; to-day is the progenitor of to-morrow. When the atmosphere is telescopic, and distant objects stand out unusually clear and distinct, a storm is near. We are on the crest of the wave, and the depression follows quick. It sometimes happens that clouds are not so indicative of a storm as their total absence. In this state of the atmosphere the stars are unusually numerous and bright at night, which is also a bad omen. It appears that the transparency of the air is prodigiously increased when a certain quantity of water is uniformly diffused through it. Mountaineers predict a change of weather when, the air being calm, the Alps covered with perpetual snow seem on a sudden to be near the observer, and their outlines are marked with great distinctness on the azure sky. This same condition of the atmosphere renders distant sounds more audible.

There is one redness of the east in the morning that means storm; another that indicates wind. The first is broad, deep, and angry; the clouds look like an immense bed of burning coals; the second is soft and more vapory. At the point where the sun is going to rise, and a few minutes in advance of his coming, there rises straight upward a rosy column, like a shaft of dyed vapor, blending with and yet partly separated from the clouds, and the base of which presently comes to glow like the sun himself. The day that follows is pretty sure to be windy.

It is uncertain to what extent birds and animals can foretell the weather. When swallows are seen hawking very high, it is a good indication, because the insects upon which they feed venture up there only in the most auspicious weather.

People live in the country all their lives without making one accurate observation about nature. The good observer of nature holds his eye long and firmly to the point, and finally gets the facts, not only because he has patience, but because his eye is sharp and his inference swift. There are many assertions, the result of hasty and incomplete observation, such as, for instance, that the way the Milky Way points at night indicates the direction of the wind the next day; also, that every new moon indicates either a dry or a wet month. There are many other stories about the moon too numerous to mention. Again, when a farmer kills his hogs in the fall, if the pork be very hard and solid he predicts a severe winter; if soft and loose, the opposite; overlooking the fact that the kind of food and the temperature of the fall make the pork hard or soft. Numerous other instances could be cited to prove that the would-be shrewd farmer does not interpret nature in the right way, and that his conclusions, being hasty and incomplete, are wrong; and until he studies nature understandingly, using a little common sense, so long will he be more or less under the ban of superstition and ignorance.

The Bell Telephone Patents Sustained.

The great telephone suit has been decided by Judge Wallace in favor of the Bell Telephone Company. The People's Company will, it is said, take an appeal to the United States Supreme Court, but they are in the mean time enjoined from putting up and operating any telephones under the Drawbaugh inventions. The suit of which the present opinion is the result was commenced in 1880, and the principal points relating thereto have already been referred to in these columns. Judge Wallace in his opinion says:

"The issues made by the pleadings are practically resolved into the single question—to which the proofs and arguments of counsel are mainly addressed—whether the patentee, Bell, or Daniel Drawbaugh, of Milltown, in Cumberland County, Pennsylvania, was the first inventor of the electric speaking telephone."

The theory of the defendants, according to the opinion of Judge Wallace, is that some of Drawbaugh's instruments were made in 1867, and others at various times before 1874.

"It is in proof that thirty-three patents were granted for improvements in telephones in 1878, sixty-four in 1879, more than one hundred in 1880, and ninety-four in the first six months of 1881. According to the theory of the defendants, therefore, as early as February, 1875, Drawbaugh had not only distanced Bell in the race of invention, but also Gray and Edison, and had accomplished practically all that has since been done by a host of other inventors."

The testimony on both sides is reviewed at length, and the Judge concludes:

"Succinctly stated most favorably for the defendants, the case is this: One hundred witnesses, more or less, testified that one or more occasions, which took place from five to ten years before, they think they saw this or that device used as a talking machine. They are ignorant of the principles and of the mechanical construction of the instruments. But they heard speech through them perfectly well, and through one set of instruments as well as the other. This case is met on the part of the complainants by proof that the instruments which most of the witnesses think they saw and heard through were incapable of being heard through in the manner described by them; and further, that the man who knew all about the capacity of his instruments never attempted to use them in a manner which would demonstrate their efficiency and commercial value, but on the contrary, for ten years after he could have patented them, and for five years after they were mechanically perfect, knowing all the time that a fortune awaited the patentee, and with no obstacles in his way, did not move, but calmly saw another obtain a patent and reap the fame and profit of the invention. Without regard to other features of the case, it is sufficient to say that the defense is not established so as to remove a fair doubt of its truth; and such doubt is fatal. . . . A decree is ordered for complainant."

Congress and the Patent Office.

The Hon. Benjamin Butterworth, Commissioner of Patents, labored earnestly during the last session of Congress to obtain from that body the relief which the Patent Office so sorely needs, in the way of increased appropriations for the employment of additional examining and clerical force, and urging the necessity for enlarged departments for the transaction of the steadily growing business of the office. Mr. Butterworth is now himself a member-elect of the next Congress. This body, however, does not meet, except it be called together in extra session, until December, 1885, and unless the present Congress takes some favorable action before its dissolution in March next, the Patent Office will continue to go on in its present crippled condition for a year, and perhaps a year and a half, to come. Mr. Butterworth succeeded last spring in getting a slight increase on the former appropriation, but his present position is such as to give added force to any effort he may now make in behalf of the inventors of the country to obtain from the Government what has only thus far been withheld by the grossest injustice.

In the mean time we trust that inventors themselves will not be entirely idle. There are enough of them in each Congressional district who have been greatly annoyed or injured by former delays in the Patent Office to exercise a potent influence on the action of their representatives. Let all such inventors, as well as those who are expecting in future to have business relations with the Patent Office, write direct to their representatives, urging prompt action on this hitherto greatly neglected matter. The present session is a short one, lasting only till March, but the appropriations now made must govern the business of the office for the year commencing next July. It is evident, therefore, that there is no time to lose, and interested parties should strongly urge that this appropriation should be one of the first considered, and not to be left to the hurry and accidents of the closing days of the session.

Madagascar.

Madagascar consists of a central plateau or highland rising from 4,000 feet to 5,000 feet above the lowlands of the coast, and from this plateau rise occasional volcanic cones, the highest, Ankaratra, being 8,950 feet above the sea. These volcanoes extend from the northern extremity of the island to the 20th parallel of south latitude. South of this appear granitic rocks, at least as far as 22° south latitude. At higher latitudes than this the rocks of the interior are practically unknown to Europeans. According to a recent paper by Mr. F. W. Rudler, F.G.S., several crater lakes and mineral springs abound; and to the north of the volcanic district of Ankaratra there is a tract of country containing silver, lead, zinc, and copper ores. As regards building stones, besides the granite which is so general, there are vast beds of sandstone and slate between the district of Ankaratra and the fossil regions in the southwest of the central plateau. These fossils, according to M. Grandidier, the recent French traveler in the interior, are referable to the Jurassic system, and comprise remains of hippopotami, gigantic tortoises, and an extinct bird of the ostrich species. The coasts of the country are rich in timber, and it would also appear that the interior is a good mineral field.

More Time for American Inventors.

For the purpose of allowing American inventors every possible facility for participating in the London "Inventions" Exhibition the time during which applications will be received has again been extended, the limit being now fixed at Jan. 31. As the exhibition opens in May next, it is hardly to be expected that there will be any further postponement, so intending applicants for space should take this as a last notice. The Hon. Pierrepont Edwards, British Consul in New York city, who will furnish the necessary printed forms for applicants, reports that the number of applications thus far from this country have been quite large, and the interest shown by our people in respect to the exhibition is quite encouraging.

Mr. Edwards is untiring in his efforts to interest American inventors in the exhibition, and he is encouraged to believe that the display of their works will be most creditable to the nation.

The Slaughtering of Cattle.

The process of killing and dressing beef at the stock yards, says a contemporary, is not as expeditious and wonderful in character as is that of killing and dressing hogs. The features most noticeable are the two methods used in killing the animal at the start. One of these methods is through the use of the rifle, and the other the lance. In both the animals are driven singly from the yard into a narrow box stall open at the top. A dozen of these stalls are in a row, and over their tops are laid some loose planks on which the slayer walks with rifle or lance in hand. In the case of the rifle the executioner puts a ball into the animal's brain at short range, which kills instantly. Not a groan is heard, not a muscle moves. The animal falls like a lump of lead, and is at once dragged from the stall into the slaughter-house, where the throat is cut and the process of dressing is completed.

© 1884 SCIENTIFIC AMERICAN, INC

EXPERIMENTS ON SUPERHEATING AS A CAUSE OF BOILER EXPLOSION.

On the 9th of April, 1883, Commandant Treve laid before the Academy of Sciences a note upon the different means proper to prevent the explosion of steam generators, and, in the course of his paper, attributed a large number of explosions to a peculiar state of the water called *superheating.*

First Series of Experiments.—The object that these had in view was a study of ebullition in ordinary glass vessels. It was desired to ascertain what importance the long preparation which physicists cause their vessels to undergo may have from the standpoint of superheating.

Balloons of good, clear glass and small dimensions were selected, and pure water and dilute aqueous solutions of three degrees. The ebullition was accompanied with violent movements of, the vessel. When vaporization was excited by one of the means indicated for superheated water, there was at times a violent ebullition accompanied with projections.

Second Series of Experiments.—These experiments were performed at the shops of the Orleans Railway, in France,



Fig 1.—Elevation. Fig. 2.—Section through *c d.* Fig. 3.—Elevation. Fig. 4.—Plan (Scale ¼).

Plate I.—EXPERIMENTS AT THE CONSERVATORY.

The Minister of Public Works having invited the Central Committee on Steam Engines to examine the processes proposed by Commandant Treve, a number of experiments were made by that body, and a report was drawn up, from which we extract the following:

Not finding in the industrial facts that have been observed up to the present any decisive proof in favor of M. Treve's theory, the sub-committee endeavored to enlighten itself through experiments, as follows:

various materials were boiled therein. The heat was obtained from a Bunsen burner, the flame of which was spread out by means of wire cloth. The temperature was given by a thermometer which dipped into the liquid. The ebullition of the pure water and of the saline and alkaline solutions gave rise to but a few insignificant movements, even when it was prolonged for some time.

Slightly acidulated water gave rise to very marked superheating, which, however, did not exceed more than two or upon the saw mill boiler, and the object of them was as follows:

It results from the experiments of physicists that superheating is in all cases favored by a stagnation of water during a more or less prolonged stoppage, having for effect the expulsion of the imprisoned air. Let but a slightly energetic action occur on the superheated liquid, and evaporation will take place and a large quantity of steam will be

(*Continued on page* 397.)



Fig. 1.—General Arrangement of Boiler and Accessories. Fig. 2.—Elevation of Boiler Front. Fig. 3.—Elevation of Rear End.

Plate II.—EXPERIMENTS AT THE TROCADERO.

© 1884 SCIENTIFIC AMERICAN, INC

THE PNEUMATIC TELEGRAPH LINE AT PARIS.

The line of pneumatic tubing, which was laid as far back as the year 1867, was, on the 1st of January, 1878, 20 5 miles in length, this representing from the beginning an average of 8,830 feet laid per year. Now the total length is 111 miles, to which must be added the 12·5 miles of tubing that secure communication with the centers of power. It includes a double main line, in which terminate 72 secondary ones, with various branches, plus a direct line between the central station and the Bourse.

The number of offices that have been opened for the service of the tubes is 75, this including those of the Chamber of Deputies and Senate.

The 111 miles of lines are supplied by 8 stations, having steam engines of a total power of 315 horses, and 4 auxiliary water motors, which can eventually be used in addition. The trains run every three minutes upon the direct line from the central station to the Bourse, every five minutes upon the principal line, and every quarter of an hour only upon the few branches. The lines consists of tubes of 2½ inches internal diameter, that are bored perfectly true, so as to present no projection that might interfere with the running of the boxes. The boxes or travelers move through the tubes under the action of compressed (or rarefied) air produced by special pumps.

After the dispatches have been put into the box, the latter is closed by means of a rubber sheath which almost entirely covers it. The last box of each train carries at its back part a sort of collar formed of a flexible leather ring 3¼ inches in diameter, whose edges, being in contact with the inner surface of the tube, obstruct the latter completely without interfering with the movement of the box. The box thus arranged is called the piston box, and performs the part that a locomotive does on railways, while the simple boxes correspond to cars. There is, however, the difference that when the passengers (*i. e.*, the dispatches) are not numerous the locomotive itself carries them to their destination. Each box is capable of containing twenty dispatches.

The apparatus shown in the engraving serve as stations for the trains, and, as in all stations, there is a starting and an arriving side. The apparatus of the same line are thus grouped in pairs, and, moreover, are exactly alike, so that, if need be, the direction of the train may be reversed. They consist essentially of a vertical tube (in which the line terminates) ending in a square chamber whose anterior face is provided with a door that closes hermetically. It is through this latter that the boxes are introduced and taken out. The curved tubes that are seen here and there upon the central tube of each apparatus serve to connect the line with the vacuum or pressure apparatus by means of cocks that are maneuvered by a small hand wheel. The large collecting tubes placed horizontally communicate through tubing with the reservoirs, in which the play of the pumps is constantly renewing the stock of compressed or rarefied air.

Finally, in case a box that has reached one of the apparatus must start again through the contiguous one without getting a vacuum or pressure from the station itself (which is something that happens in all intermediate offices that are not connected directly with a center of power), it is necessary that the compressed or rarefied air shall be capable of traversing the station in order to drive the train toward the following stations. The two chambers that form the heads of the apparatus are then connected by opening a cock placed upon a connecting tube situated behind. In order to prevent a box that has reached the head of an apparatus from falling into the line, the tubist, as soon as a train arrives (which he knows through the noise of the shock), closes the line by means of a valve maneuvered by a lever that is within his reach. In the annexed figure the three apparatus to the left have their valves closed, that is to say, they are isolated from their lines. The fourth alone is in a position for receiving or sending.



NEW SYSTEM OF PNEUMATIC TUBES AT THE CENTRAL TELEGRAPH OFFICE, PARIS.

The play of the valves is likewise utilized for preventing the compressed or rarefied air that fills the line at the moment of a train's arrival from being lost in the atmosphere when the door of the apparatus is opened.

The figure also shows several indispensable accessories. The pressure gauges indicate at every moment the degree of pressure or vacuum—an attentive examination of the movements of the needle upon the dial clearly showing to an experienced agent any irregularities that may occur in the running of the "piston." A manipulator placed over the door, and an electric bell surmounting the "cap" of the apparatus, serve for exchanging starting and arriving signals.

Finally, a series of iron plate sheaths serve for holding the exchange boxes. The velocity of the boxes varies with the length of the line and the amount of power that determines their motion. Under favorable circumstances, that is to say, upon very short lines, and with a difference of pressure of 40 centimeters of mercury, the velocity may reach six-tenths of a mile per minute.

The entire line will be finished this year, and telegram cards will soon be circulating in all the wards.—*La Nature*

ACCORDING to the theory of F. Siemens, flame is the result of an infinite number of exceedingly minute electrical flashes, which are caused by the swift motion of gaseous particles.

IMPROVED REFRIGERATING CARS.

The object of an invention recently patented by Mr. Henry Tallichet, of Austin, Texas, is to provide an improved system of refrigeration and apparatus for applying the same to practical use. The body of the car has any approved double or packed walls serving as non-conductors of heat, and suitable side doors. The car is fitted with two chill rooms, one near each end, and of a size to afford free air spaces at the sides and ends, the center air space being wider for access to the rooms through their doors. These rooms are jacketed with a porous material, and rest upon a slat floor, beneath which are water tanks in which may be stored water or ice, with the drippings of which the porous jackets are kept saturated by a pump located in the center air space, and having suitable pipe connections for discharging the water on to the top of the rooms. The pump is operated from one of the car axles. The bottom of the tank descends each way to a well formed by a depression, and into which the suction pipe extends. Air is forced into the space between the top of the tank and floor on which the rooms rest by one or more blowers, driven from the car axle, for evaporating the water from the jackets to lower the temperature of the rooms. The water not evaporated flows back into the tank, and as but little escapes, a continuous supply is not needed. To increase the air draught the roof of the car is provided with ventilating fans, and although these may induce sufficiently strong air currents, the blowers are a valuable auxiliary. When the car is not moving the blowers are inoperative, and to guard against a rise in temperature, ice chambers opening near their tops for supply of ice are located over the the chill rooms. The devices described provide for cooling the rooms in every exigency of travel and without recourse to independent motors.



TALLICHET'S IMPROVED REFRIGERATING CAR.

Near the bottom of the ice chamber is placed the central portion of a continuous pipe, having a zigzag construction, which serves as a rack to hold the ice and keep it above the drip water. This portion of the pipe is set in an inclined position, and at one end has a branch passing outward and downward and opening to the outer air, and at the other end has a branch passing down into the chill room. Air enters the pipe, and as it passes through the zigzag part in the ice chamber is deprived of its moisture by condensation, and appears in the chill room in a pure, cool, and dry condition, best suited for purposes of ventilation. The incline of the worm permits of a self-discharge of the condensed vapors. At a point as far removed as possible from the cold air outlet, there is passed into the chill room the open end of a pipe the other end of which opens into the case of one of the exhaust fans at the roof. This pipe acts constantly to exhaust and circulate the air of the chill room, thereby avoiding the deleterious effects of "dead air." An arrangement is provided for reducing the temperature of the chill room by saturating its top and side walls with the cold water drip of the ice chamber; this is accomplished automatically and at any premeditated temperature by an electrical contrivance acting on a valved outlet from the ice chamber. The water escaping from the ice chamber fills a shallow tray formed on the chill room roof by narrow ledges, and flows down the sides of the room, materially reducing the interior temperature.

This apparatus is automatic in action, and uses no chemicals as refrigerating agents. The quantity of ice used is reduced to a minimum, as its effects are required only, or principally, when the other means fail by stoppages of the car.

© 1884 SCIENTIFIC AMERICAN, INC

A Suggestion to Employers.

The Bridgeport (Conn.) *Daily Standard* hits the nail on the head when it recommends a year's subscription of the SCIENTIFIC AMERICAN as the best Christmas present an employer can make his workman, or a father his son. The editor further adds:

"And let any manufacturer try the experiment of asking each man in his employ as to the interest he would take in reading such a periodical if it was placed before him, and he will be surprised at the amount of pleasure and choice information that can be furnished at a small outlay. For every paper thus put in the hands of his employes he would receive four times its value by reason of the increased interest which would be taken in whatever work might be in hand, to say nothing of the benefit which would be directly derived from the enhanced skill of the workmen. The weekly visits of the periodical would constantly remind each man that his employer was concerned in his welfare, and that he had exerted himself to show that interest. We know from personal experience that information gained from the columns of the scientific journal above mentioned is invaluable to the person who is interested in science, art, or natural history, and it would be truly a pleasure to learn that we had induced even one employer to take a step which he would ever afterward be satisfied was a good one."

We await to see how many will follow the good suggestion of our valued contemporary before this month closes. —ED.

Putnam River, Alaska.

The Ounalaska (Lieut. G. M. Stoney, U.S.N., commanding) arrived in San Francisco, October 25, having completed the exploration of Putnam River so far as the time allotted would permit. The river was explored by a steam launch three hundred miles, when rapids were encountered; then a canoe was taken and towed by hand about eighty miles further; and from this point a short portage brought a portion of the party to the head waters of one of the northern tributaries, which was fed by two large lakes. A mountain near one of these lakes furnished a view far to the eastward, up the main valley of Putnam River, and showed it flowing in undiminished volume as far as the eye could reach. The natives reported that seven days' journey further up the river there was a great lake, looking like a sea; and it is thought that this is the source of the river. There is little doubt that the river has its origin as far east as the British possessions, and probably near to the Mackenzie.

Putnam River empties into Hotham Inlet just north of Selawik Lake and to the southeast of Kunatuk River. There is a large delta at its mouth stretching back about forty miles, which is pierced by over one hundred channels, one of which is about one mile in width. The river is navigable to boats drawing from five to six feet of water, up to the rapids. Here the water flows at about ten knots per hour. The river and most of its tributaries lie within the Arctic circle. Most of the tributaries are from the north, and they are generally shallow but rapid flowing, while the water is very cold; in some instances the observed temperature being 38°, while in one case it was 33°. Only one considerable branch was found flowing from the southward. This is called the Pah River by the natives, and it is used by them in journeying to the south; for a very short portage from its source enables them to reach one of the northern tributaries of the Yukon River, and they are thus brought in easy communication with the trading posts. It is believed that like easy portage can be made from the Putnam to the river discovered by Lieut. Ray near Point Barrow, and which empties into the Arctic Ocean.

The country about Putnam is mountainous. Long ranges extend along either side, but they are peculiar in existing in small detached groups, each of which possesses distinguishing characteristics, some being clearly defined, sharp, rocky peaks, while others are smoothly rounded. The higher ones are estimated at about three thousand feet. From the tops of those which were ascended the whole country to the north appeared to be a confused mass of mountain peaks, and the natives stated that the country was of the same character to the Arctic Ocean.

The country explored was found to possess a warm and agreeable summer climate, the thermometer having reached 115° in the sun, while the nights were cool. The valley of the Putnam is heavily timbered with spruce, birch, cottonwood, larch, and willow; while flowers were in abundance, roses being seen in large numbers. Cuttings of these latter, together with specimens of coal, gold, and copper, and a huge fossil trunk, form a part of the material collected for the Smithsonian Institution.

While Lieut. Stoney was absent, Ensign Purcell remained with two men in charge of the schooner, and made a survey of Hotham Inlet and the Selawik. He found that the Selawik River represented on the charts has no existence; but there is a channel, six miles in length, connecting Selawik Lake with a chain of three lakes to the eastward. He also found a five fathom channel over the Hotham Inlet bar.

The Ounalaska is a fifty-four ton schooner, and Lieut. Stoney was provided with two officers and a crew of eight men. There were no naturalists with the expedition.

While returning from his expedition, Lieut. Stoney encountered several severe gales. During one of the most severe he employed oil for stilling the waves, with marked success. The oil was rigged upon a spar to which a drag was attached, and the vessel was so maneuvered that the drag stood off the weather bow. The vessel holding the oil was so constructed that the oil was forced out in portions by each advancing wave. All the waves were affected by the oil, but the great foaming combers most markedly.

PATENT DRAWERS.

The top part of the drawers is made of woven or knit linen or cotton fabric, and the legs are made of the same material down to or a little behind the knees, and the lower part of the legs are of open work fabric. The perforated part of each leg is provided with an upright slit in the usual manner, and with bands or buttons at the lower end to hold the drawers leg securely, and at the same time prevent the socks from slipping off. The apertured parts permit of a free circulation of air, thereby keeping the legs cool and making the drawers comfortable and agreeable during hot weather. The front of the upper part of the drawers is



TOWLES' DRAWERS.

closed perfectly, one side overlapping and buttoning upon the other.

This invention has been patented by Mr. Wm. P. Towles, of 145 Baltimore Street, Baltimore, Md.

COMPOSITE MICA SHEET.

An invention recently patented by Mr. John L. Rorison, of Bakersville, N. C., is specially designed to meet the wants of retailers of stoves, who, with punch, rivet, and hammer, can join two or more small pieces of mica to form a sheet of any size and shape. Figs. 1 and 2 represent the completed sheet of mica, Fig. 3 shows the pieces separated, and Fig. 4 is a section through the rivet. In uniting four pieces the inner corner of each piece is slightly cut away, so that when they are put together a central opening will be formed for the passage of the rivet. The inner edges of each sheet are notched, so that when put together the edges lap past each other, forming good joints, and are at the same time locked in place. The contiguous edges being placed together, the rivet is inserted, when the washer is put upon the smaller end and the rivet headed down, thereby causing the head of the rivet and the edges of the washer to grasp and firmly hold the pieces. When only two pieces are used to form



RORISON'S COMPOSITE MICA SHEET.

the sheet, the edges are notched to form the lock joint, and the centers of the adjoining edges are cut away to make a passage for the rivet.

Civil Service Reform in Mines.

The recent mine explosion in the Connellsville region has led the mine inspectors to take steps to prevent a repetition of these horrors. This morning the inspectors met in this city. They will draw up a bill to present to the Legislature, in which miners ignorant of the business will be excluded from the mines. Pit bosses and men having charge of the ventilating of the mines will be required to pass a thorough examination before taking a position. It is also proposed that the inspectors move for establishing a school for the purpose of furnishing free instruction to men whose purpose is to engage in coal mining.

Magic Photographs.

What are called magic photographs are positives printed in a latent state upon white paper that it is only necessary to immerse in ordinary water to have the image appear.

The means employed for obtaining this curious and surprising effect are as follows: The positives are printed, from any negatives whatever, upon paper sensitized with chloride of silver, such as may be purchased of any dealer in photographic supplies. The printing is done with the aid of sunlight, either direct or diffused, in an ordinary printing frame, or, more simply, between two plates of glass held together by means of spring clips.

The image, when once printed, is fixed in a bath composed of 10 grammes of hyposulphite of soda dissolved in 100 grammes of ordinary water. It is not toned with gold, but is thoroughly washed with water after coming from the bath, so as to remove every trace of the hypo from the fibers of the paper.

This washing is absolutely necessary, in order that the paper may remain perfectly white after it has been treated with the following bath:

Bichloride of mercury	5 grammes.
Water	100 "

The image, when immersed in this bath, soon gradually begins to lose color, and finally disappears altogether. When the paper has become entirely white, it is washed in water and allowed to dry.

If it be desired to cause the latent image to reappear, it is only necessary to immerse the paper in a weak solution of hyposulphite of soda, or better of sulphite of soda.

To the back of these photographs there is attached a piece of bibulous paper impregnated with sulphite of soda. In this way, when the paper is immersed in water, the sulphite at once dissolves, and the image quickly appears.

The bichloride of mercury (corrosive sublimate) is a substance that should be used only with great precaution, as it is a violent poison. Care should therefore be taken to allow no delicate part of the body to come into contact with it, and to put the vessels containing it in a safe place out of reach.

The sensitive paper adapted for this curious recreation may be either albumenized or salted simply.

The sensitizing is performed by floating upon a 10 per cent nitrate of silver bath, for five minutes, either salted paper that may be purchased in this state or be easily prepared by immersing white paper in water containing 5 parts of table salt to 100.

After sensitizing, the paper is suspended by one corner, and allowed to dry in a dark place. For the balance of the operations one will proceed as above directed.

The *rationale* of the phenomenon is as follows: The image formed by the light is colored by the reduced silver. This image, when bleached by the bichloride, contains both calomel (chloride of mercury) and chloride of silver. Sulphite of soda possesses the property of dissolving chloride of silver, and of blackening chloride of mercury by forming a sulphide. —*Leon Vidal, in La Nature.*

How to Keep Cider Sweet.

Pure sweet cider that is arrested in the process of fermentation before it becomes acetic acid or even alcohol, and with carbonic acid gas worked out, is one of the most delightful beverages. The *Farm, Field, and Fireside* recommends the following scientific method of treating cider to preserve its sweetness. When the saccharine matters by fermentation are being converted to alcohol, if a bent tube be inserted air tight into the bung, with the other end into a pail of water, to allow the carbonic acid gas evolved to pass off without admitting any air into the barrel, a beverage will be obtained that is fit nectar for the gods.

A handy way is to fill your cask nearly up to the wooden faucet when the cask is rolled so the bung is down. Get a common rubber tube and slip it over the end of the plug in the faucet, with the other end in the pail. Then turn the plug so the cider can have communication with the pail. After the water ceases to bubble, bottle or store away.

Shameful Treatment of Inventors.

The fact that the revenues of the Patent Office are largely in excess of its expenditures is an unanswerable argument in favor of the very considerable increase of the clerical force in that office. American inventors do not ask to have reduced the fees which must be paid to get a patent. What they want is that their applications shall receive immediate attention, and that the money demanded of them shall be used to secure this for them. As the matter now stands, they are compelled to pay for that which they do not get. They are forced to submit to long and often ruinous delays because there are not enough clerks in the office to do the work, and meantime the money which they pay to have the work done is suffered to lie idle and accumulate until it now amounts to a fund of two or three million dollars. It would be difficult, we think, to conceive of anything more asinine than such an arrangement.—*The Textile Record.*

It is too bad, as our contemporary says, with such a large amount to the credit of the Patent fund, that the Patent Office should be crippled in its usefulness for the want of a sufficient clerical force to attend to the business, owing to a lack of a little Congressional wisdom. The inventors of the country are not small in numbers or weak in influence, and it is incumbent upon them to use their individual influence with the Congressmen from their respective districts in respect to the necessities of the Patent Office.

© 1884 SCIENTIFIC AMERICAN, INC

EXPERIMENTS ON SUPERHEATING AS A CAUSE OF BOILER EXPLOSION.

(*Continued from page* 394.)

quickly emitted. Such a thing occurs at the moment of starting a generator that has slowly cooled during an entire night, with register and ash box closed, and with a fire covered uniformly with cinders. It was of interest, then, to ascertain whether, under such circumstances, the opening of the steam port, by causing an ebullition, would not bring about a sudden forward motion of the pressure gauge.

The boiler experimented upon was a tubular one, having the shape of that of a locomotive, and the following dimensions: Heating surface, 65·4 square meters; capacity of the water reservoir, 3,130 liters; capacity of the steam reservoir, 1,089 liters.

During its normal operation this boiler vaporized about 425 liters of water per hour. It was heated by wood.

Observations were made on the 22d and 23d of June, 1883, and were resumed on the 11th of July, and continued every day till the 1st of August. In the morning, at the moment of setting the boiler in operation, and while the steam port was being opened, an observer had his eyes fixed upon the pressure gauge. But these observations showed absolutely nothing abnormal in the movements of the gauge. If the fire was quick at the moment of starting, the pressure continued to rise until the engine had acquired its normal speed; and, when the fire was covered, the pressure slowly lowered.

Third Series of Experiments.—In a boiler in normal operation the temperature of the steam is the same as that of the water. If, at a given moment, the water becomes superheated (to take that particular state in which it ceases to vaporize), the tension of the steam becomes independent of the temperature of the water, and there must, therefore, occur a difference between the temperature of the two. An endeavor was made to seize differences of such a nature, and, with this end in view, a series of experiments was planned in which the differences of the temperature of the steam and water of a boiler should register themselves for a long time.

The arrangement adopted for taking the temperature is shown in Plate I., Figs. 1 to 4.

The boiler experimented upon was that of the Conservatoire des Arts et Metiers. It was a cylindrical one, having four lateral feed-water heaters, a heating surface of 13 square meters, and a grate surface of 27·5 square decimeters.

A thermo-electric pile was constructed for suspension in the boiler in such a way that a series of solderings should dip into the water, while others of equal number should remain in the steam. This pile, which was 45 centimeters in length, consisted of 15 iron wires and 15 German silver ones, 1·5 millimeters in diameter, soldered successively by their extremities. These wires were arranged according to the generatrices of a boxwood cylinder, 40 millimeters in diameter, having an aperture running through it lengthwise for the passage of the copper wire by which the pile was suspended vertically from the self-closing cover of the manhole of the boiler.

The ends of contrary polarity, which remained free, were connected with a galvanometer needle, whose deflections were registered every quarter of an hour upon a sheet of paper by means of a puncture made by a vertical point fixed to the needle's extremity. This registering apparatus, with clockwork movement, was the same as had been successfully employed by Gen. Morin for measuring at the different points of a ventilating chimney, the excess of internal temperature over that of the surrounding air.

Each positive experiment included the registering, every twenty-four hours, of the position of the galvanometer needle, before firing up and until the boiler was under pressure, at the time the engine was set running, and while the latter was operating under nearly a constant pressure, and finally during the period of cooling, up to the next day or day after. Then the paper was changed in order to obtain a new diagram corresponding to the firing up again, before or after a new feed, until the pressure had risen to the normal one of five atmospheres, and had permitted the engine to run regularly.

No notable deviation was exhibited in the position of the galvanometer needle during all these alternations, or during the whole duration of the observations, which were greatly prolonged.

It resulted from an examination of the diagrams that the temperature of the steam pole was in general not quite so high; but the difference was always below 2°. This is explained by the proximity of the sides of the boiler, the temperature of which was naturally lower than that of the steam, and which radiated against the steam pole.

During the night of August 26–27, the galvanometer needle became strongly disturbed, as shown by the tracings. What was the cause of it? We do not know; but, at any event, the form of the tracing does not permit it to be attributed to superheating, seeing that the movements occurred between half-past one and six o'clock in the morning, that is to say, during the period of cooling. Further, the diagram shows that the deflections of the needle occurred suddenly and disappeared slowly, while the contrary would have taken place had superheating been the cause of the movements.

It is thus established by direct experiment that no appreciable difference is shown between the temperature of the water and that of the steam during any of the periods comprised in the observations, either during the running or during firing up or cooling.

Fourth Series of Experiments.—Finally, it was desired to ascertain whether, by depriving water entirely of the air in solution, by means of an extremely prolonged ebullition, the phenomenon of superheating could not be obtained in a metallic boiler.

The experiments were performed at the laboratory of the Ecole des Ponts et Chaussees, at the Trocadero.

The boiler, A, used (see Plate II., Figs. 1 to 3) consisted of an iron cylinder provided with strong cast iron heads. This was tested to a pressure of 15 kilogrammes per square centimeter. Its capacity was about 21 liters, and it was heated by a large Bunsen burner, B, having two crowns, one of them carrying 6, and the other 12 jets. The gas pipe was provided with a pressure regulator, C. By varying either the number of jets or the pressure of the gas, the conditions of heating could be modified within wide limits. The boiler was provided with the following accessories: A good Bourdon pressure gauge, D, divided into quarter kilogrammes; a water gauge, E; a safety valve, F; and various cocks. It was also provided with two horizontal mercurial thermometers that passed through stuffing boxes, G and H, and the bulbs of which entered, one of them, the water, and the other the steam. Their tubes were external to the boiler.

The arrangements made for obtaining a prolonged ebullition were as follows: From one of the cocks, I, which debouched a little over the center of the boiler, branched a tube that bent so as to run nearly to the bottom of a vertical cylindrical vessel of water, K, made of galvanized iron. The water in this reservoir had been previously boiled, and the same was the case with that which was to be added from time to time to replace the water which had evaporated. The capacity of this vessel was 50 liters.

The boiler being heated, the steam produced bubbled up through the water in the vessel, K, and kept it at a boiling point. As the cover of K had but two narrow apertures, one of them for the passage of the steam pipe, and the other for the exit of the excess of steam, it will be seen that there always existed at the surface of the ever hot water in K an atmosphere of steam, and that the water could not dissolve any air.

The operation was as follows: The boiler was heated for about an hour and a half, and then the gas was shut off. Through the condensation of the steam by cooling, the boiler became completely filled with water drawn from K. In half an hour, heat was again turned on, when there flowed through the feed pipe, first, water, and next steam. For alternately admitting and cutting off the gas, a small apparatus was used that consisted of a hydraulic working beam, L, which maneuvered the gas cock, M.

The boiler had been cleaned with caustic potash, and then washed with a large quantity of water. The apparatus was set running January 4, 1884, at 3 o'clock P. M. The experiments, properly so-called, began January 15. The water had therefore boiled, before the first experiment, for eleven days, night and day, with an interruption of half an hour every two hours, corresponding to about 200 hours of continuous ebullition. It may be admitted that on the 15th of January the boiler and water were absolutely devoid of air.

During this entire period the two thermometers were observed from time to time, and were always found to agree within about one or two degrees. Such difference we have already explained in our account of the Conservatoire experiments.

The experiments, properly so called, were performed on the 15th of January and the days succeeding, and were as follows:

All the cocks were closed, and the boiler being submitted to the action of heat, the temperature and pressure consequently rose. At intervals, simultaneous observations were made of the thermometer which dipped into the water, of the one which was in the steam, and of the pressure gauge.

Finally, the conditions of heating were varied, so as now to cause the temperature to rise 50° in half an hour, and then to rise only 28° in six hours and a half.

The last experiments were performed after the boiler had been kept closed, and slightly heated for nearly fifteen hours, and the result of them may be summed up as follows:

The two thermometers were constantly in accord; the difference, which was always less than 2°, as in the Conservatoire experiments, is very naturally explained by a few small variations in the construction of the instruments and the action of pressure upon their bulbs, and especially by the unequal effect of radiation from the sides of the boiler. It was remarked, in fact, that the thermometer in the steam gave lower indications than the other when the pressure rose, and, on the contrary, higher indications when it lowered. At the moment of opening the escapement no abnormal movement in the needle of the pressure gauge was ever seen.

Conclusions.—In conclusion, the committee believes that it has in no wise been demonstrated, up to the present, that the superheating of water has caused any boiler explosion, nor that superheating has ever occurred in generators used in the industries. If it does occur, it is only in extremely rare cases, and through the concurrence of exceptional circumstances that are up to the present neither defined nor known. There is, therefore, no need for the moment of examining the remedies that have been proposed for preventing the superheating of water in generators.

DESCRIPTION OF PLATE I.—P, thermo-electric pile; *pp'*, wires for connecting the poles of the pile and the galvanometer, G; Q, needle of the galvanometer, G, that moves around the axis of the suspension wire, *g*; *c*, cam of the registering apparatus, moved by clockwork and allowing the disk, D, to rise every 15 minutes under the action of the weight, F; T, man-hole, closed by the cover, H, which latter is provided with two stuffing boxes, *r*, *r'*.

PLATE II.—A, boiler; B, Bunsen burner; C, pressure regulator; D, Bourdon pressure gauge; E, water gauge; F, safety valve; G, thermometer in steam; H, thermometer in water; I, feed cock; K, freed water tank; *b*, steam eduction aperture; *c*, water gauge; *d*, blow-off cock; L, hydraulic working beam fed by the bottle, *e*; M, gas cock; N, lighter; *f*, blow-off cock of the boiler; *g*, escape pipe.—*Abstract from Annales des Ponts et Chaussees.*

Acetate of Soda Heaters.

For the last two years experiments have been making toward the warming of cars by means of a heat giving fluid, which continues for several hours to throw out heat with approximate regularity, for a time depending upon the original degree of heat imparted to the liquid. The cars of the De Kalb Avenue line in Brooklyn, seventy in number, have been heated by this system during the last winter to the satisfaction of the company, and presumably to that of the public.

A large iron pipe containing the compound passes under each seat of the car; through the center of the pipe runs a smaller pipe, through which steam is passed when it is desired to heat the compound. When heat is applied to the pipes from a steam boiler in the station, the crystals in the acetate of soda used are liquefied, and remain so until the temperature begins to fall perceptibly. Then the crystals begin to form, and the liquid throws out an increased heat. A thermometer taking the temperature of a pipe of the heated compound shows that during the first hour or two there is a slight fall in the temperature, then a sharp rise while crystallization takes place, and then a gradual fall.

A record of the temperature of one car kept during twenty days showed that after each run of sixteen miles, the temperature of the car was upon an average less than one degree lower when the car returned to the station than when it started out. The cost of heating cars by this system is said, by the company which controls the patents, to be not more than for stoves, while the heat is pleasanter and the atmosphere is free from gas and smoke. The compound in the pipes will last for an indefinite number of years, for all that is known to the contrary, being hermetically sealed.

This company now propose to introduce the same system as an improvement on heating by ordinary steam radiation. Steam coils often heat too violently in small rooms, and either give too little or too much heat. By using the steam to heat a reservoir of the compound liquid, the steam can be turned off when the room is sufficiently warm, and the reservoir will continue to throw out a constant amount of warmth for several hours. A small pipe full of the compound, 3 feet long and 4 inches in diameter, is made for heating private carriages.

Earth Worms.

An interesting paper on the habits of earth worms in New Zealand is contributed to the New Zealand Institute by Mr. A. T. Urquhart. The species are not named, but with such wonderful opportunities as Mr. Urquhart possesses for making a collection of these, may we hope that, in addition to his following out his painstaking observations as to their habits, he will also advance science by making a careful collection of the forms and placing them in the hands of some of the able naturalists of the Auckland Institute for description? It will be remembered that Darwin assumes that in old pastures there may be 26,886 worms per acre, and that Henson gives 53,767 worms per acre for garden ground and about half that number in corn fields. Mr. Urquhart gives, as the result of his investigations of an acre of pasture land near Auckland, the large number of 348,480 worms as found therein. It being suggested to him that in his selection of the spots for examination he may have unconsciously selected the richest, the experiment was again tried in a field seventeen years in grass. A piece was laid out into squares of 120 feet, and a square foot of soil was taken out of each corner; worms hanging to the side walls of the holes were not counted, and in one hole, where the return of worms was a blank, the walls were crowded with worms. As a result there was an average of 18 worms per square foot, or 784,080 per acre. Although this average is very striking when compared with that of Henson, it is worthy of note that the difference between the actual weight of the worms is not so marked. According to Henson, his average of 53,767 worms would weigh 356 pounds, while Mr. Urquhart finds that the average weight of the number found by him came to 612 pounds 9 ounces.

Indelible Stamping Ink.

E. Johanson, of St. Petersburg, gives the formula for a convenient ink for marking clothing by means of a stamp: 22 parts of carbonate of soda are dissolved in 85 parts of glycerine, and triturated with 20 parts of gum arabic. In a small flask are dissolved 11 parts of nitrate of silver in 20 parts of officinal water of ammonia. The two solutions are then mixed and heated to boiling. After the liquid has acquired a dark color, 10 parts Venetian turpentine are stirred into it. The quantity of glycerine may be varied to suit the size of the letters. After stamping, expose to the sun or apply a hot iron.—*Pharm. Rec.*

© 1884 SCIENTIFIC AMERICAN, INC

THE MAXIM MACHINE GUN.

(*Continued from first page.*)

motion carries the catch free of the stop, and a little more lifts the catch, by its tail coming in contact with the stop. The bolt aud the barrel are then free of each other, and the former receives a rapidly accelerated motion from a lever pivoted on the barrel, and moves with it. As the barrel approaches the end of its stroke the point of the lever meets a stop, and commences to rotate about its pivot. In doing this it forces forward a piece connected to the block, first with a slow motion and then with a gradually augmenting one, as the leverage of one arm increases and that of the other diminishes while the lever rolls over the stop and the piece. By the action of the lever the barrel is arrested, while the block and the mechanism attached to it continue to move until the crank, I, gets on to the back center. As soon, however, as the block has commenced to leave the barrel, and before the latter has come to rest, the extractor, M, strikes the peg which stands in its path, and turning on its pivot on the barrel, draws the shell about ¼ inch out of the gun. This extractor has two arms, shown in dotted lines, which take hold of the empty cartridge at each side, and withdraw it with certainty. The extraction is completed by a hook shown (Fig. 5) attached to the crosshead.

This hook runs under a fixed spring, which is curved upward at each end to reduce the pressure when the shell is being started, and when it is about to be released. The empty cartridge case is deposited in one of the pockets of the cylinder, G, which is partially rotated just as the crank reaches the back center, and is carried round to be dropped out after the next shot. This cylinder is visible in Fig. 4, where a shell is seen in the act of falling out. The partial rotation of the cylinder brings the next pocket, which has already been charged, into a line with the barrel, and now the first series of operations is complete. The recoil has taken place, the breech block unlocked, the shell first started, and then completely extracted and removed, and the new car tridge brought into position for loading.

The next series, which is about to commence, consists in cocking the hammer or striker, pushing the cartridge home, locking the breech piece, and releasing the sear. As the crank approaches the back center the tail, D, of the cocking lever meets the stud, J, and the catch is caught and detained by the sear. The main spring, which is somewhat indistinctly shown coiled round the striker, is thus compressed, and held ready for action. When the crank has passed the center the breech block moves toward the barrel, pushing the cartridge before it until the latter is home and the block is locked by the catch, C.

The momentum of the crank and crosshead is sufficient to carry the barrel forward until the toggle arms, *d d*, pass the center, and the springs, *e e*, are in a position to urge it to the end of its travel. If the gun is set for very rapid firing they do this immediately, and the sear coming into contact with the cam, K, the striker is released, and the cartridge fired. After the shots have been fired the same cycle of operations is repeated, with this difference that the crank, instead of starting from the position shown in Fig. 5, occupies the dotted position, and commences to rotate in the opposite direction. It never makes a complete revolution. But if the gun be not set for a rapid rate of firing, there is a pause after the breech is locked, and the length of the time is determined by the adjustment of a hydraulic buffer, resembling in principle a cataract cylinder. This appliance (L, Fig. 5) consists of a piston working in a cylinder with a by-pass between its two ends. This by-pass is a plug, and is provided with a handle working over a quadrant on the outside of the case. This quadrant is marked for speeds between *nil* and the maximum, according to the opening which is afforded between the two ends of the cylinder at the various angles. The rate of fire can be reduced in practice to one shot in every twenty-five seconds, and by very careful adjustment to one in fifty seconds. The operation of the hydraulic buffer is as follows: Upon the upper side of the barrel is a stop which, just before the end of the forward stroke, meets the piston of the buffer, as clearly shown in Fig. 5. Under the influence of the springs, *e e*, it forces the liquid through the plug until the barrel has moved far enough to lift the sear, and then the explosion takes place. There is a valve in the piston of the buffer to allow it to be returned quickly by a spring during the recoil of the barrel.



Fig. 3.

This completes the description of the introduction, firing, and extraction of a cartridge, but it remains to explain how the charges are withdrawn from the belts mentioned above, and introduced into the pockets of the cylinder, G. The full belt is drawn out of the magazine (Figs. 1 and 4), and passes over the wheel, F, which has recesses in each flange for the ends of the cartridges to rest in. This wheel is geared to the cylinder, G. In the firing position a hook or extractor, E, stands below the cartridge, and when the crosshead goes back this catches a cartridge and draws it into a pocket on the underside of the cylinder, where it leaves it to be carried upward to the barrel by the rotation of the cylinder. The empty belt is fed out of the opposite side of the machine (Fig. 4), and the lengths can be taken apart by unhooking and refilled ready to be fed in again.

The external handle of the hydraulic buffer also acts as a trigger, for if the by-pass be opened when the gun is loaded the explosion follows instantly, while if it be entirely closed the gun cannot be fired. As a means of precaution the sear is mechanically locked when the by-pass is stopped. The crankshaft is carried through the casing, and is furnished with a handwheel which is worked in starting the gun until the first fire has taken place. It is also used whenever a faulty cartridge, which will not explode, stops the action. In such case a single revolution throws out the obstacle, and the automatic action is at once resumed.

The gun stands about 3 feet high, and is 4 feet 9 inches from the muzzle to the rear of the firing mechanism. It can deliver any number of shots per minute from two or three to six hundred, the latter being, of course, a kind of trial trip performance, under favorable conditions. At all rates, it is perfectly steady, and the gunner is perfectly free to concentrate all his attention upon the aim, without having his vision or his steadiness interfered with by turning a handle. No one can fail to be struck, says *Engineering*, to which we are indebted for these notes, with the wonderful ingenuity and great promise of this new weapon. Its automatic action, its power of regulation, and its rapidity of fire must recommend it to the military authorities, while its steadiness and the small demands it makes upon the attention of the man in charge must greatly enhance its value in action, where it is not the number of shots, but the number of hits, that count.



Fig. 4.



Fig. 5.—THE MAXIM SELF-ACTING MACHINE GUN.

A New Electrical Lantern.

An attempt has been made by Mr. A. P. Trotter to construct lanterns which shall diffuse powerful lights, such as that of the electric arc, without incurring the loss entailed by the use of opal glass. This was done with certain lamps fixed at the Health Exhibition, by a special modification of prismatic lenses (such as are used for lighthouses), adapted for ordinary lanterns. The general shape of the lanterns is the same as that of the more improved street lanterns for powerful gas flames—an inverted cone closed at the top by an opal glass cap in the form of a much flatter cone. The glazing of the lantern, however, instead of being with plane glass, is with specially moulded panes, bearing on them a number of prisms at one-fourth inch pitch. The prisms are formed on both sides of the glass, those on the front being borizontal, and those at the back running vertically. The effect is to break up the light source into a multitude of images of itself; care being taken that the angle of the prisms does not give a chromatic effect. Each pane so formed, for a 2 foot 6 inch lantern, is 14 inches long, tapering from 8 inches wide at the top to 2 inches at the bottom; and ten of these go to form the lantern. It is claimed that the absorption of light by such a lantern is only 10 or 15 per cent, as against 40 to 60 per cent with ground or opal glass.

A New Camera Lucida.

A new camera lucida has been invented by Dr. Schroder, possessing many advantages over the well known contrivance of Dr. Wollaston. The pencil emerging from the eye piece of the microscope is reflected twice, as in the old instrument, but the view of the paper and pencil is obtained by means of another prism placed under the first; the pencil from the microscope is totally reflected, and cannot pass through the film of air between the prisms, and the paper is seen directly between the two prisms, which offer no more obstruction to the view than a thick piece of plate glass.

The position of the image does not shift when the eye is moved, and the painful strain caused by the bisection of the pupil in the Wollaston instrument is entirely avoided. Drawings can be taken either with the body of the microscope at the usual inclination of 45°, or in a vertical position, both more comfortable in every respect than the old horizontal one, and preventing disturbance of the illuminating arrangement by having to shift everything when a drawing is required.

© 1884 SCIENTIFIC AMERICAN, INC

SOME SPECIMENS OF FINE CATTLE.

The accompanying representation of a select herd of cattle is from the pencil of Mr. Cecil Palmer, who has obtained considerable distinction in making pictures of this class; our engraving, for which we are indebted to the courtesy of the *Rural New-Yorker*, being a reduced copy of an original 28 by 36 in in size. The cattle represented all belong to the same family, the Aaggie, a breed imported from Holland, and now in possession of Messrs. Smiths & Powell, of Syracuse, N. Y.

At the right stands Neptune, the head of the family, and lying down in the foreground is Aaggie Kathleen; she has given this season, the first after her importation, 9,525 pounds of milk in seven months and five days to Nov. 1. Aaggie Beauty, standing in the water, has a milk record of 80 pounds 6 ounces in a day. As a three-year-old in Holland she gave 68½ pounds in a day; as a four year-old she gave, the first year after importation, 13,573 pounds, and made in one week 10 pounds of butter. Just above this one is Aaggie, having a milk record of 18,004 pounds 15 ounces in a year, and next behind her is Aaggie Beauty 2d, a daughter of Aaggie Beauty, who has given this season, as a three year-old, 7,793 pounds in seven months and six days to Nov. 1. At the left in the background is Aaggie Rosa, who as a five-year-old in Holland gave 91 pounds in a day, and last season gave 16,156 pounds in the year. The one in the right of the background is Aaggie May, the dam of the calf shown, and she has given this season, as a three-year-old, 57 pounds 13 ounces in one day, and 8,705 pounds in six months and sixteen days to Nov. 1.



SOME SPECIMENS OF FINE CATTLE.

Ardea Cœrulea.

Reader, I see before me a small lake or pond, lying in a vast tract of pine forest, unbroken, save here and there by the clearing of the settler who has cast his lot in this sunny clime of Florida; a pond that is decked here and there with beautiful water lilies, beneath which lies the alligator, ever ready to catch him who dares intrude on his domains; a pond wherein dwells the deadly moccasin, and whose shores are covered with a rank growth of wild oats and trees from which hangs the long Spanish moss—a landscape pleasing to the eye, but seen only by him who seeks Nature in all her glory. It is such a place as this that the little blue heron inhabits, and to which I shall take you for a glimpse of him as he is when freest from the fear of danger, and when pursuing his natural vocations. The little blue heron (*Ardea Cœrulea*), sometimes called the little white heron, is a constant resident of Florida, frequenting the small ponds, lakes, bayous, and lagoons, where its food is to be found, and where I have seen them assembled six or eight in number. The young are pure white in color (hence the name little white heron), from which they change to the dark blue color as they grow older, which, if I am not mistaken, they acquire in their third year.

Should there be a number of ponds near by, they seem to give preference to some certain one, at which they may almost always be found, unless previously frightened away, when they betake themselves to the next, where if they are not followed they remain for a time, and in the course of an hour or so wend their way back to the aforesaid pond. Now let me describe to you some of the habits of these birds, as I have observed them when lying in concealment on the shores of one of these ponds. Young and old feed together in perfect harmony, and a beautiful sight it is to see the snowy white plumage of the young birds intermingled with the dark blue of the old.

How proudly and yet how stealthily they step through the tall grass in search of their food! Suddenly one pauses, darts his beak at an insect, and again pursues his way. Yet in their chosen haunt they are constantly on the lookout for danger; pausing, they raise their long necks, and peer about them closely for some cause of alarm; assured that all is safe, they again betake themselves in search of whatever they may fancy as an article of diet.

Presently, one in his wanderings comes to a log lying partly on land, partly in water; mounting this, he proceeds to dress his plumage and to sun himself. With head drawn down between the shoulders, he stands motionless for an hour at a time, and it might seem as though he were asleep, but not so; let him hear but the snapping of a dry twig in the woods, and instantly every nerve is on the alert. Stretching out his neck, he gazes intently in the direction of the noise, and should he perceive sufficient cause for alarm, he immediately springs into the air together with the rest of his companions, who are not far off, when unless fired at they generally alight on the opposite shore, and seek refuge in the tall grass, or else alight in a tree. Should the one, however, who first heard the noise perceive no cause for alarm, he sometimes signals to his companions in some way, when they all arise, and fly a few times over the spot, and then alight again.

Let us now suppose that they have alighted in a tree where we can see them plainly. There they sit pluming themselves, but yet keeping a sharp lookout to see if they are followed. If everything remains quiet after a lapse of ten or fifteen minutes, they begin to fly down one at a time. Close at hand lies the upturned root of a fallen tree; on this they alight first, then from there they fly to the ground. The last one to leave his perch usually tarries a few moments as if to take a last look, then he also flies down and joins the rest, when they soon work their way to some favored spot.

When perched on a tree they carry their body in an oblique position, at an angle of about 45°; but when walking on the ground or when wading in the water in search of food, it is horizontal, or perhaps the breast is carried a trifle below the tail. The way in which they carry their necks when flying is different from their near relative, *Ardea Herodias* (great blue heron), being the shape of a broad, shallow U, with the head a little higher than the shoulders, whereas in *A. Herodias*, it is folded similar to a reef. Should they be suddenly approached, they fly away with a hoarse, harsh, croaking noise.

Occasionally they stroll for some distance into the woods, for the beetles, insects, etc., to be found there. I have seen them forty to fifty rods from the water. When there they sometimes rise and fly a few yards, and then alight again; in such cases they do not fly higher than four or five feet from the ground. I have never seen these birds in the rushes; they seem to prefer the grass from two to three feet high on the shores. Their manner of alighting is different from that of other herons. When about to alight, they throw themselves back into the air perpendicularly, with wings and tail widely expanded, and neck partially drawn in (representing as near as possible the screens that are made from them by taxidermists), then glide toward the spot selected, pause an instant, wheel, and alight. Sometimes these birds become so far accustomed to civilization that they will approach quite close to a building from which much noise proceeds. To illustrate: I saw one alight on the shore of a pond, in plain sight of and within a stone's throw of a large saw mill (which at the time was running at full speed), and remain there until frightened away by the mill hands. I have never heard this bird utter any note, except the note described when suddenly surprised, and then only when surprised.

Description: Length, 22⅝ in.; extent, 38 in.; iris light yellow in both stages of plumage. Bill dark blue at base, black at tip. Lores yellowish blue, tarsus pea green, toes pea green, claws blackish drab. In white plumage, mostly white, but generally showing some traces of blue, especially on the wing tips. In the full or blue plumage, slaty blue, or dark grayish blue, becoming purplish red or maroon colored on the neck and head. Bill on loral space, blue, shading to black toward the end. Legs and feet black.

E. M. HASBROUCK.

THE oldest person in the State of Wisconsin, John Jondro, aged 121 years, died on Saturday morning, Nov. 29, 1884, at Arkansaw. Mr. Jondro was born in the parish of Phillip, near Montreal, in 1763. He was in the employ of the Northwestern Fur Company forty years, and during the last forty years he has lived in this neighborhood. In his younger years he served some time in the Federal army, and often related interesting tales of army life. His age is taken from the statement of the parish prelate of Phillip.

© 1884 SCIENTIFIC AMERICAN, INC

Artificial Sea Water for Aquaria.

The following, by Prof. R. E. Hoffmann, of Berlin, is translated in the *Bulletin of the United States Fish Commission:*

In former years hardly any salt water aquaria were found in inland countries, because the expense and trouble of furnishing a constant supply of salt water were too great. Even the Berlin Aquarium, with its abundant funds, was so far from the nearest sea coast as to make the supply of natural sea water uncertain, and it suffered from this condition of affairs. The people of Berlin wittily called this chronic condition of their aquarium its "sea sickness." Although every new institution has to pass through a period of so-called "children's diseases," this peculiar "sickness" of the Berlin Aquarium proved very obstinate, and even threatened the life of the young and tender child whose birth had been hailed with so much joy. The Vienna Aquarium had to pass through similar experiences, and the stockholders were obliged to pay dearly for the experiment. As matters stood at the Berlin Aquarium, the use of artificial sea water seemed very desirable; but many a well planned experiment based on scientific principles proved a failure; for, although the component parts of sea water are well known, and any chemist can easily prepare it from a receipt, it seemed at first impossible, in a chemical way, to breathe the "breath of God" into our scientific sea water, and to impart to it the secret of true vitality. At last, however, long after the institution had been opened, Dr. Hermes succeeded in solving the problem in a scientific manner, and proved in the most incontrovertible way that the maintenance of inland salt water aquaria was no longer dependent on the nearness of the sea coast. Dr. Hermes succeeded in satisfying every demand, as regards sea water, within one week.

The very bold assertion of the director of the zoophyte aquaria in the zoological garden in Regent's Park, London, that artificial sea water, even if a chemical analysis cannot discover the least difference between it and natural sea water, is never beneficial to animals and plants, has been disproved by the success of the Berlin Aquarium. Since we have succeeded in manufacturing artificial sea water which possesses all the qualities necessary for the life of animals and plants, and which, by the use of suitable apparatus, can be kept fresh for years, nothing prevents inland towns from having sea water aquaria, which, in many respects, are peculiarly interesting.

As sea water aquaria have a great future in Germany, and will rapidly increase in number if proper directions for their maintenance are given, I will describe the manufacture of the water in such a manner that any one can easily prepare it himself. To 50 liters (about 13¼ gallons) of pure hard well water take 1,325 grammes (46½ ounces) of common salt, 100 grammes (about 3½ ounces) of sulphate of magnesium, 150 grammes (about 5¼ ounces) of chlorate of magnesium (chlormagnesium), and 60 grammes (about 2 ounces) of sulphate of potassium, all of which can be obtained at any drug-store, but generally not entirely pure; and foreign admixtures and impurities may easily cause the death of all the animals. Each of these chemicals is dissolved in water by itself; accordingly they may all be poured together and allowed to stand quietly for several hours, so that little stones and other impurities may settle to the bottom. All particles of dirt floating on the surface should be carefully removed by dipping. The mixture is then poured into another vessel, and diluted with fresh water until the hydrometer indicates the proper degree of saltness. The quantities given above will produce about 50 liters (about 13¼ gallons) of sea water.

This composition I have ascertained comes very near to that of natural sea water, for, besides the component parts given above, it also contains small quantities of soda, iron, and potash. I obtain the chemicals for preparing my sea water, which contains all the seven ingredients in their true proportions, from a friend of mine who is a chemist, and am prepared to supply others. Most of the sea water found in the market contains only the four first mentioned salts, and is likewise suitable for filling the basin. One should be careful, however, not to put animals in such freshly manufactured sea water, as this would almost beyond a doubt kill them. It is well known that sea water is 0·027 gramme heavier than fresh water; its weight is therefore 1·027. Everything lacking in this weight must be carefully added from time to time by pouring in fresh water as the water evaporates, while this is not the case with the salts. The solid ingredients of sea water constitute about 3½ per cent of its weight, or one-half ounce to a pound of water. A hydrometer is indispensable for ascertaining the degree of saltness.

Newly manufactured sea water should be placed in the open air in some cool place, and allowed to stand for some time. If one has any live salt water algæ adhering to stones they should be added, because they impregnate the water with oxygen. After some weeks the algæ will spread all round them clouds of diminutive seeds, which adhere to the walls, and quickly grow under the influence of light. By supplying oxygen they make the water, after it has been filtered several times, still more fitted to receive animals. Of sea plants, the green ulvæ and the confervæ are particularly suitable for recently manufactured salt water.

In the beginning only a few hardy animals should be placed in the water, which will flourish and thrive in it; and after a while an attempt may be made with more tender animals, which, if placed in the water in the beginning, would probably have died. If no algæ can be obtained, the water should be allowed to stand longer. Any one who can afford to wait until a green cover of algæ spreads over the panes, will do well to defer placing the animals in the water till that time, and a little patience is very commendable during the entire process. Like wine, salt water, if properly treated, improves with age, as special apparatus continually supply it with oxygen by night, and keep it agitated. The water in the Hamburg Aquarium has not been changed for fifteen years, and is still perfectly clear, transparent, and odorless, in short, of the very best quality; and all that has to be done is to make up for accidental losses or evaporation. The water of the salt water aquarium is changed or filtered only when it begins to get turbid, or if some change is to be made in the arrangement of the aquarium. It will always be advisable, however, to keep at least a double supply of sea water on hand, and place it in the cellar in well corked bottles, as any sudden emergency will then be fully met.

I have never been able to obtain natural sea water which was as clear as the artificial, through which one can see everything distinctly, even in the most remote corner of a large aquarium, which it would be very difficult to do in natural sea water. I have brought up sea water in a dipper which, when poured into a glass, was as clear as crystal and had a brilliant blue color; but this is possible only on the high seas, and when the water is brought up from a considerable depth. Fishermen take too little care and trouble in this respect: close to the shore they will dip up the water resembling a thick, yellow, and stinking juice, and ship it to other places. For this reason I use artificial sea water prepared in the manner indicated above, and even without adding any plants I succeed in keeping my animals alive.

It is self-evident that the principal point in constructing salt water aquaria is the treatment of the water, which, after all, is the element which decides the well-being and sickness, life and death, of the animals. Care should be taken to keep the water well supplied with oxygen, which is easily done by means of the aerating apparatus; and to see to it that the normal proportion between the salts and sea water is always maintained, and as soon as anything appears to be wanting in this respect, it should be supplied. As soon as the water begins to get turbid it should be filtered, and during an abnormal state of the weather it should be cooled. Only when these conditions are fulfilled will it be possible to keep up a successful salt water aquarium; only thus shall we be enabled to have in our rooms an exact representation of the bottom of the sea, with all its mysteries and wonders. I, therefore, repeat in conclusion, "The treatment of the water is the main thing."

A Florida Woman Who Runs a Sawmill.

The following letter, written to the *Northwestern Lumberman*, contains a number of homely truths that apply to all sorts of mechanical work:

Your letter of a late date requesting me to give my experience as a lumber manufacturer is at hand. I will state at the start that I am not in the business through choice; but having loaned money to parties with which to purchase a saw mill, I was compelled by their failure to make even the first payment to take the machinery from them. I then put my son-in-law, Ernest Wever, who promised great things, in charge. I told him I knew nothing of sawmilling, but I knew that the sawdust was too fine and the scratches on the boards too close together. I left him to run the mill, but in a short time I found he could do no better than other men, and I took him out of there so quick it made his head swim. I moved the mill a distance of 20 miles, fording the Hillsborough River, and placed it near my own house, at an actual expense of $9; and in a few days I had everything in good order. I have my own teams and carts, and take timber from my own lands.

Although accustomed to manage my own affairs, commencing by the time I was grown, I found difficulties enough in making lumber, and I have often said that a sawmill and Satan belong in the same family, and some people say that since I became the owner of one they are sure of it; but while they talk I am at work. This is the trouble with half the country sawmills: There is too much talking and not enough work. Why, Mr. Editor, the most of men talk over a log long enough to saw it into inch boards. Then when they get started they discover that the fireman has not steam enough; then they must all sit down and talk again. By the time steam is up and one or two boards sawed, a belt must be repaired, which might just as well have been attended to before working hours in the morning or at noon. Then one man sews the belt while all engage in talk again. When the belt is ready, the sawyer gets it into his mind that the machinery needs oiling; then he hunts up the oil can, for he never has a place for anything, and goes around squirting oil into every hole but the right one, while the other hands go on with their talking. The next day they are out of logs, and the mill hands do nothing except to allow "their time to go on." The day following some of the men are reported sick, and more time is lost. At the end of the month there is little lumber and no money, and they all wonder why sawmilling does not pay.

I knew well enough that machinery is made to run, and when running it should be at work, and all I had to do was to keep the saw cutting for ten hours a day and six days in the week. In order to do this the mill must be kept in good order, not by repairing broken parts, but by keeping it from getting broken. And I soon saw that the parts of machinery out of sight were neglected the most. I would suppose any man would know that it is the inside of things that needs attention—the inside of the boiler, the inside of the cylinder, the inside of the pump or inspirator is of far more importance than the outside. Nothing makes me more angry than to see a man rubbing up the outside of his boiler when I know the mud is six inches deep inside, baking, burning, and blistering the iron; yet I have seen but few saw mills except my own. But I saw how that was managed before I took possession of it, and I am told that others are managed no better.

Many a man in the sawmill business would do well if he could get skilled labor, but this State is cursed with a tribe of sawmill tramps who claim to know everything, and when tried can do nothing. They are always on foot and out of money, yet if we are to believe them they have been the superintendents of the largest mills in America. Every one of them has been Governor Drew's principal sawyer for at least ten years, receiving not less than $6 a day. They all know more of machinery than the men who make it, and are ready, not to commence sawing, but to commence cutting, changing, splicing, and rebuilding, with a promise that if I will give them $3.50 per day and board they will double the capacity of my mill and be ready for work in about three weeks. I have never been deceived by one of them, but they leave their mark wherever employed. One-half of them ought to be hung and the other half sent to the penitentiary. One came to me a few days ago who was an exception, for, notwithstanding he was "the best sawyer in Florida," he was willing to work for $10 a month and board, or $12 if he boarded "hisself"—hungry looking wretch! I wouldn't have boarded him even a day for $2, and I knew he couldn't board himself at any such price. Said I, "Do you see that road out there?" He very meekly said he did. "Then," said I, "you go out there, and when you get to it you take either end you like; the one that will put you out of my sight the quickest will suit me the best." He went. If he had not, I would have put the dogs after him in three minutes.

I employ none but the best hands—not paying too much or too little, for one fault is about as bad as the other.

I can't say just what my lumber costs me, but I know that when sold I have taken in more money than I have paid out. I am 53 years old, or about that, was born in Florida, and was raised at a time when bookkeeping was not thought of.

I now have my second husband, and I am the mother of nine children, seven of whom are now living. Several of the elder are doing business for themselves, yet they always come to "mother" for advice, and when they don't take it they wish they had. I have always managed my own business, and I expect to while I live. I awake in the morning and plan the day's work while the men are asleep, and at the breakfast table I give every one his orders, including my husband, who never objects to my doing the thinking for the family.

My first advice to men who contemplate going into the sawmill business is—don't do it, for not one in twenty of you has the ability to succeed. If, however, you are determined to try it, be careful that you get the best machinery, strong and heavy enough to stand the bad treatment of awkward hands. Buy the most durable belts, no matter what they cost, for half the failures in our backwoods mills are caused by constant breaking of belts. And when a complete outfit is secured, locate where you can get timber and sell lumber. Keep your machines in good order, taking special care of all parts out of sight. Pay your hands in cash, and not in promises, for they work for the money, and not for any love they have for you or your business. When you can't pay, shut down, stack your lumber, and discharge all hands. Your mill will neither eat, drink, nor wear anything while standing still. But when you do run, work everything to its full capacity. HARRIET SMITH.

Tuckertown, Fla., November 17, 1884.

A Bird Catching Tree.

Among the transactions of the New Zealand Institute Mr. R. H. Govett gives some startling facts as to the bird-killing powers of *Pisonia brunoniana* or *P. sinclairii*. A sticky gum is secreted by the carpels when they attain their full size, but is nearly as plentiful in their unripe as in their ripe condition. Possibly attracted by the flies which embalm themselves in these sticky seed vessels, birds alight on the branches, and on one occasion two silver-eyes (Zosteropos) and an English sparrow were found with their wings so glued that they were unable to flutter. Mr. Govett's sister, thinking to do a merciful act, collected all the fruit bearing branches that were within reach and threw them on a dust heap. Next day about a dozen silver-eyes were found glued to them, four or five of the pods to each bird. She writes: "Looking at the tree, one sees tufts of feathers and legs where the birds have died, and I don't think the birds could possibly get away without help. The black cat just lives under the tree, a good many of the birds falling to her share, but a good many pods get into her fur, and she has to come and get them dragged out."

In a note Mr. T. Kirk says that *Pisonia umbellifera*, Seeman = *P. sinclairii*, Hook. f., is found in several localities north of Whangerei, both on the east and west coasts, also on the Taranga Islands, Arid Island, Little Barrier Island, and on the East Cape, possibly in the last locality planted by the Maoris. The fruiting pericarp is remarkable for its viscidity, which is usually retained for a considerable period after the fruit is fully matured. It can be readily imagined that small birds tempted to feed on the seeds might easily become glued to a cluster of fruits.

© 1884 SCIENTIFIC AMERICAN, INC

On Steel Hardened by Pressure.

The new process invented by M. Clemandot for hardening steel was lately examined by M. Ad. Carnot, and made the subject of a report presented by him, as a chairman of a committee, to the French Societe d'Encouragement for National Industry. The method in question consists in heating the metal to the proper degree of softness, and submitting it while cooling to heavy pressure. The result is the formation of a hardened steel possessing properties similar to those developed by the operation of quenching.

The remarks and explanations contained in M. A. Carnot's paper are quite interesting and practical, but somewhat lengthy. We give below a condensation of the most important points.

The use of strong pressure in working steel, he says, was tried some years ago in England by Whitworth, but with a different object and under different circumstances. Then the idea was to prevent the flaws due to air bubbles forming during the solidification of cast steel. Similar trials were also made in France, but always in the same manner, that is, by operating on the steel while yet in the semi-liquid state. M. Clemandot, on the contrary, takes steel already worked, either cast, hammered, or rolled, which he only heats to cherry-red heat, and then submits, under a hydraulic press, to a pressure of from one thousand to three thousand kilogs. per square centimeter (about six and a half to twenty tons per square inch). The metal is allowed to cool in the press, and when withdrawn has acquired the new qualities, and needs no annealing or supplementary process whatever.

The metal thus produced sensibly differs from ordinary steel slowly cooled in the air without pressure. It is much finer grained, and considerably harder and tougher. To a certain extent it resembles steel hardened by quenching in water, yet the two are not identical.

On examining the process it will be seen that it consists of two physical effects, different although nearly simultaneous. One is continuous and powerful pressure; the other rapid cooling.

Strong pressure must cause, on one hand, a rise of temperature in the metal, and also a tightening of the steel molecules while they are yet soft enough to weld together. On the other hand, the cooling of the steel must be very rapid between the plates of the hydraulic press. It must be all the more so that a high pressure tends to render the contact very close between the objects and the heavy metallic plates of the press. Hence the final result of the operation is a double one: it combines to a certain extent the effects of hammering or rolling with those of hardening by quenching in water.

To better understand where the old processes and the new one differ and where they are similar, it is well to examine separately the various methods of working steel.

HAMMERING AND ROLLING.

When steel is heated to redness, and allowed to cool slowly, it is apt to acquire a granular structure, often at the same time allowing a part of the combined carbon to separate in the state of graphite. The operations of hammering and rolling the metal, while yet very hot, prevent to a certain extent the granular change, render the steel tougher and more homogeneous, and lessen the proportion of carbon which is lost in the shape of graphite. These operations, however, last but a short time, so that on being left to itself the metal soon crystallizes again, and in the end is not very different in texture from what it would have been if it had been left alone.

The effect of the hydraulic press must be quite dissimilar. The actual pressure, it is true, cannot equal that produced by the pounding of heavy hammers, but it is uninterrupted while the objects are cooling. Hence the molecules of the metal are possibly welded together permanently, thus forming a very tough and elastic steel.

TEMPERING.

The tempering of steel appears to have the effect of preventing the metal from crystallizing. Whether mercury, oil, pure water, or saline water be used for quenching, the principle is the same, and consists in a rapid cooling of the metal. The results are *chemical* and *physical*.

The *chemical* effects are still imperfectly known, yet it is generally admitted that steel contains, after quenching, a larger proportion of combined, or rather dissolved, carbon than before, while untempered steel contains more free carbon in a state resembling graphite. The chemical effects of tempering may therefore be said to closely unite the carbon and the iron, or to prevent the separation of the two substances already combined.

The *physical* effects are more complicated than is generally believed. At first the exterior strata contract on cooling, and strongly compress the internal portions, still soft and malleable, in such a way as to probably weld together the molecules of the metal. This first action may be compared to that produced by hammering the red hot steel.

But now a secondary action begins, which is quite different, and all the more noticeable that the piece is larger. At the moment of the sudden hardening of the surface the inside layers are yet hot and strongly dilated. Hence, when the latter, on cooling in their turn, tend to contract, the external strata having become hard and rigid cannot follow the motion, and this must create unequal tensions between the various sections of the steel.

There are no direct experiments proving the truth of this theory, but two facts indirectly show its correctness. One is the decrease observed in the specific gravity of steel when it is tempered. The other is the internal cracking so frequently noticed in large pieces of tempered steel, and which occurs sometimes at the moment of quenching, sometimes shortly afterward, and again after a longer delay, when the piece is struck or exposed to changes of temperature.

If it is considered that the internal inequality of tension above alluded to may become so considerable as to rise above the tenacity of the metal, the cause of these cracks becomes readily intelligible.

The remedies proposed for these fatal defects have all been either useless or impracticable. Among them the quenching in boiling water succeeds to a certain extent, but fails to afford the hardness obtained otherwise. The plan of cooling from the center instead of the exterior is excellent in theory, but almost impossible in practice.

HARDENING BY PRESSURE.

A mistaken idea must be, to begin with, brushed aside. It has been written by some that hardening by this process could only be obtained by pressure in a mould of the exact dimensions of the steel object.

Such is not the case. The pressure needs only be applied to two opposite surfaces of the object, previously heated to a cherry red heat. A square bar, for instance, straight or curved into horseshoe shape, has only to be laid flat on the plate of the hydraulic press. A cylinder or torus may have the pressure applied on two opposite edges, and so forth. As a rule, of course, it is advantageous to apply the pressure to the greatest surfaces. To work under the best conditions the steel object, previously heated as said above, should be compressed as speedily as possible. To this purpose the press is prepared so as to leave between the two plates space just sufficient to admit the object, and the pressure being applied at once, is carried as quickly as possible to the extent fixed beforehand. Care must be taken also that the metallic plates, which are in direct contact with the object, be clean and level, so as to be good heat conductors.

Thus the double result mentioned above, is obtained, namely, a tightening if not a welding of the steel molecules, owing to the powerful and uninterrupted action of the press, and at the same time, through contact with cold metallic masses, a rapid chilling similar to quenching in a liquid. And yet there is between the two processes this essential difference, that steel tempered by immersion increases in volume, thereby decreasing in specific gravity, while under the action of the hydraulic press steel retains its original volume, and escapes the state of internal distention already spoken of. Direct experiments have proved that *a priori* theories are confirmed by actual facts.

MAGNETIC EFFECTS OF COMPRESSION.

Between ordinary tempered steel and compressed steel there exists one more similarity, namely, the acquired power of forming magnets. A steel bar sufficiently rich in carbon becomes, after hardening by pressure, readily magnetized, just as if it had been hardened by immersion. Recently instituted trials have demonstrated that magnets made with compressed steel are slightly inferior in power to those composed of ordinary tempered steel, but the metal possesses the singular property of retaining its coercive force even after annealing and welding. Like ordinary steel it loses its magnetization on being heated to redness, but while common steel must be tempered again to make a magnet, compressed steel can be magnetized without further preparation.

The conclusions of the report are that M. Clemandot's invention deserves encouragement, as affording a new process for imparting to steel the hardness, homogeneousness, and capacity for magnetization hitherto obtained through tempering by immersion; certain disadvantages of this last process are at the same time obviated. It is the opening of a new way worthy of investigation.

Poisonous Cheese.

At the October meeting of the American Public Health Association at St. Louis, Professor V. C. Vaughan, M.D., of the State Board of Health of Michigan, read a paper on the "Study of Poisonous Cheese." It is well known that cases of severe illness follow the eating of some cheese, especially in North Germany and America, but in France no such cases are found. In Michigan, within the last six months, over three hundred cases of cheese poisoning have been reported. The symptoms produced are dryness of the throat, nausea, vomiting, diarrhœa, headache, and double vision—the same symptoms as gastro-intestinal poisoning. Cases of cheese poisoning are rarely fatal, six deaths in three hundred and forty-two cases occurring in Holland in 1874, a little over two per cent. Cheese that may be harmful to man may be eaten by lower animals without danger, and a cat once ate cheese that had poisoned thirty people, but the feline experienced no toxic effect. Coloring cheese with annatto may be looked upon, perhaps, as a justifiable adulteration. Samples of cheese that had poisoned many people indicated the presence of acids, litmus paper turning blue. The indications then were that the poison was caused by chemical acids and not by bacteria. Microscopic examination, however, revealed the presence of a spherical bacillus subtilis which did not affect a cat when injected beneath the skin. Only poisonous cheese violently reddens litmus paper, and this is a test easy of application. Every grocer should try the experiment when he cuts a new cheese. The following are the conclusions: 1. That toxic material in poisonous cheese is a compound soluble in acohol. 2. The production of this poisonous material is due to the rapid growth of the bacillus subtilis. 3. The difference between poisonous and non-poisonous new cheese is one of degree rather than of nature.

The Process by which Steel Pens are Made.

A representative of the New York *Sun* has been investigating the steel pen manufacturing business of this country, and reports as follows:

About a million gross of steel pens are worn out every year in the United States. What becomes of them? Twenty years ago most of the steel pens used in this country were imported. Now comparatively few are imported, and there are several factories in the country in which they are made in large quantities. One factory is in Connecticut, another is in Pennsylvania, and a large one is in Camden. The manufacturers say that the industry has been fostered by the protective tariff, and that if the tariff were to be taken off, the market would be flooded with cheap steel pens at lower prices than ours and of inferior quality. At present the importation of foreign pens is mainly confined to high priced articles.

It was at first doubted that steel pens could be made in this country, but it was soon learned that the requisite skilled labor could be obtained for high wages, and the success of the pioneers led one manufacturer after another into the business, until now the field is pretty well supplied. Most of the work on these little instruments is done with the aid of very nice machinery worked by women and girls. The steel used is imported, because it is believed that the quality is more uniform than American steel. This uniformity of quality is necessary because of the very delicate tempering required in the manufacture of the pens. That mysterious quality of steel which gives different grades of elasticity and brittleness to different colors of steel is a quality that requires expert manipulation on the part of the workman who does the tempering. He must know the nature of the material with which he works, and with that knowledge must exercise a celerity and skill that seizes upon the proper instant to fasten the steel at a heat which insures the requisite quality.

First the steel is rolled into big sheets. This is cut into strips about three inches wide. These strips are annealed, that is, they are heated to a red heat and permitted to cool very gradually, so that the brittleness is all removed and the steel is soft enough to be easily worked. Then the strips are again rolled to the required thickness, or, rather, thinness, for the average steel pen is not thicker than a sheet of thin letter paper. Next the blank pen is cut out of the flat strip. On this the name of the maker or of the brand is stamped. The last is a very important factor. There are numbers that have come to be a valuable property to manufacturers. Many clerks say they cannot work to advantage unless they have particular styles of pens. The result is that by passing the word from one writer to another a market is soon created for a favorite style. Each steel pen has therefore to be stamped with sufficient reading matter to identify it thoroughly. The stamping is done with very nicely cut sharp dies that cut deep and clean, so that the reading matter will not be obliterated by the finishing process. Next the pen is moulded in a form which combines gracefulness with strength. The rounding enables the pen to hold the requisite ink, and to distribute it more gradually than could be done with a flat blade.

The little hole which is cut at the end of the slit serves to regulate the elasticity, and also facilitates the running of the ink. Then comes the process of hardening and tempering. The steel is heated to a cherry-red, and then plunged suddenly into some cool substance. This at once changes the quality of the metal from that of a soft, lead-like substance to a brittle, springy one. Then the temper of the steel must be drawn, for without this process it would be too brittle. The drawing consists of heating the pen until it reaches a certain color. The quality of the temper varies according to the color to which the steel is permitted to run. It is the quick eye for color and the quick hand to fasten it that constitutes the skill of the temperer of steel. When the steel is heated for tempering, it is bright. The first color that appears is a straw color. This changes rapidly to a blue. The elasticity of the metal varies with the color, and is fastened at any point by instant plunging in cold water.

The processes of slitting, polishing, pointing, and finishing the pens are operations requiring dexterity, but by long practice the workmen and workwomen become very expert. There have been few changes of late years, and the process of manufacture is much the same that it was twenty years ago, and the prices are rather uniform, ranging from 75 cents to $4 a gross, according to the quality of the finish. The boxes sold almost universally contain a gross.

Fancies come and go in the styles of pens as in other fashions. One American maker alone turns out about 350 different patterns. Some are very odd, such as the stub pens, the draughtsman's pen, which makes two parallel lines at once; the mammoth pen, suited to use on rough paper; and the pen with the turned-up point, that writes a thick mark, yet runs smoothly over the paper. Then there are delicate pens for ladies, pens that make a fine hair line and yet can spring out to a heavy shading. Already the American steel pens have become famous abroad, and many are exported. Many pens are made of other metals besides steel. One kind is the German silver non-corrosive pen for red ink. Another is an imitation gold pen made of non-corrosive metal. There are pens of all colors and sizes for all trades and professions.

© 1884 SCIENTIFIC AMERICAN, INC

ENGINEERING INVENTIONS.

An electro-magnetic car uncoupler has been patented by Mr John D. Reed, of York, Neb. There is a pivot d shackle on the drawhead with an electro-magnet for operating it, conductors, contact strips on the ends of the cars for uniting them, with numerous parts and details of combinations, whereby cars may be uncoupled by electricity.

A vessel and apparatus for cutting channels in water ways has been patented by Mr. John Gates, of Portland, Oregon. The vessel has propelling apparatus and a movable rudder, with tanks or compartments for sinking the stern to any desired depth, a hoisting apparatus, and cables with anchors, to hold the stern in position to cut a channel by the backwash from the screw.

A pilot car has been patented by Mr. Jose Pesana y Pinol, of Madrid, Spain It has transverse partitions with buffer springs, with a water tank and bar or block of lead held transversely on the car, the side bars and braces having hinges, so the car can collapse, and the springs, water tank, and lead take up the force of concussion, the car being adapted to be coupled to the front of a locomotive to lessen danger or loss from collisions.

AGRICULTURAL INVENTIONS.

A potato planter has been patented by Mr. Joseph L. Ullathorne, of Memphis, Tenn It consists of a frame, rolling drum with wheels, and an open sided hopper arranged behind, and will also distribute a fertilizer in the furrows at the time of planting the potatoes.

A combined sod cutter, seeder, and harrow has been patented by Mr William F Hubbard, of Wal la Walla, Washington Ter. This invention covers a special construction and combination of parts in a machine mounted on wheels, to be drawn over a field by a team, to pulverize hard soil, and at the same time drop and cover seed therein.

A cultivator has been patented by Mr. Thomas E. Gregg, of Mineral Spring, S. C. This invention covers a novel construction and combination to facilitate the cultivation of cotton and other plants planted in rows or drills, and also to promote convenience in adjusting the cultivator to work deeper or shallower in the soil.

A spade wheel plow has been patented by Hiram Skillings, of Minneapolis, Minn. This invention covers modifications and improvements in the construction of a spade wheel plow previously patented by the same inventor, the changes being principally with the view of reducing the expense of manufacture, and to promote convenience in putting in and removing the spades.

A stalk cutter has been patented by Messrs. Guernsey W. Davis and George A Davis, of Pine Bluff, Ark. A cutter roll has end disks with radial grooves on their inner surfaces and hubs on their outer central faces, wings with blades secured thereto being held in said grooves, and other novel features for breaking down two rows of corn, cotton, or other stalks, and cutting them into pieces.

A harrow has been patented by Mr William W Robinson, of Odebolt, Iowa. The teeth are carried by rocking beams under control of a lever to change the angular position of the teeth relatively to the ground, but the beams are of novel construction, with peculiar means for fastening the teeth as well as for carrying the beams and connecting them with the devices by which they are rocked

MISCELLANEOUS INVENTIONS

A nut lock has been patented by Mr Seth A Lesan, of Mount Ayr, Iowa This invention consists in a special construction and combination of a screw bolt, a screw nut, washer, and key for securing nuts upon screw bolts.

A gate has been patented by Mr Absalom King, of Wawpecong, Ind. This invention relates to gates adapted to close by their own weight, on farm and other roads, to prevent the straying of stock and to this end covers a special construction and combination of parts.

A weather board gauge has been patented by Messrs. William J. Dyer and Thomas W. Maxey of Nevada, Mo. This invention provides a means for carpenters to more accurately space weather boards, and hold them exactly in proper relation to previously placed boards, while nailing them in position

A log turner has been patented by Mr. William F. Fidler, of Rock Cave, West Va. This invention provides special means, in combination with the hook and tackle, the carriage, and its knees or blocks for preventing the log from sliding laterally out of place while being turned.

A copy book has been patented by Mr. Edward P Conner, of Alameda, Cal. It includes a book support, which may be shut up with the book or spread out and extended, a novel arrangement of covers and other special features, designed to afford a copy book which will facilitate giving instruction in penmanship

An ale faucet protector has been patented by Mr. George Hirschman, of Morristown, Pa. It has a flanged base, with an opening and recess in front, so it can be easily secured in place, and the faucet readily applied, detached, and operated, so the faucet will be protected.

A wire fence has been patented by Mr. Lafayette W. Lindley, of Danville, Ky. It is a fence which can be erected or taken down very rapidly, and folded compactly for storage or shipment, and is an improvement on a former patented invention of the same inventor.

A window bead fastener has been patented by Mr. Ezra W. Talbott, of Napoleon, Ohio. This is an improved device for holding the stop of a window in place on the frame in such a manner that it can be readily removed or secured in place, and need not be nailed or screwed.

A stencil holder has been patented by Mr. John W. Bennett, of Halifax, N. S., Canada. This invention covers a peculiar construction and arrangement of two clamp plates or frames for holding the stencil plates, and means for fastening the plates together and preventing them from moving laterally.

A piano forte attachment has been patented by Mr. Emil Hofinghoff, of Barmen, Germany. This invention covers a bar held to be movable across the strings, a series of tongues being fastened to the bar, and these tongues having rubber surfaces facing the strings, whereby the tones of the piano are changed.

An anchor support and tripper has been patented by Mr. Rufus P. Trefry, of Bridgewater, N. S., Canada. The anchor is so made as to hold by the fluke, while its stock comes against the hull of the vessel, and it is also so constructed as to facilitate its casting off without danger of fouling.

A game apparatus, or a new and improved game, has been patented by Mr. James A. Fitzgerald, of Salt Lake City, Utah Ter. It is formed of a vertically slotted board held between two side pieces or standards rubber face plates being secured on the surfaces of the bars between the slots, and the game being played with a series of disks or flat rollers.

A device for transmitting power by belts and pulleys has been patented by Mr. Nicholas Yagn, of St. Petersburg Russia. This invention covers a means of using pressure rollers upon both driving and driven pulleys to increase the power transmitted by belts, with the design of thus increasing their efficiency and economizing in amount of belting needed.

An improved universal joint has been patented by Mr. Rollin H Gleason, of Egan, Dakota Ter. The invention consists in providing one of two abutting ends of two shafts revolving in the same direction, but meeting at an angle with a socket, which has an inwardly projecting rib or flange upon its opposite interior sides, with other novel features.

A shield for brooms has been patented by Messrs. Neil W. Dew and Columbus F. Robertson, of Charleston, Ill. A safety shield of novel construction is made to cover that portion of the broom where the straws are joined to the handle, and thus largely dispense with the labor of winding and braiding, while giving a neat and durable finish.

An inkstand has been patented by Mr. Morris Herzberg, of West Point, Ga. It has a removable apertured tube, with a spring, and a vertically reciprocating dip cup resting on the spring within the tube, with other novel features, so there is no danger of covering the pen holder with ink, and if the ink stand is upset only the ink in the dip cup will be spilled.

A hoop fastener has been patented by Mr. William D Richardson of Springfield, Ill. This invention consists of a flat metal key, with converging rows of projecting barbs on one side and a flange or lip on the other side at the end, the key to be driven between the hoop and the barrel staves, with its barbs in contact with and burying in the wood, and the end flange turned outwardly and forming a shoulder.

An apparatus for painting wire fences has been patented by Messrs Alonzo L. Marsau and Henry C Hull of Milton, Iowa This invention relates to apparatus in which revolving brushes are supported in a paint reservoir moved along the wire, and provides for moving the apparatus continuously without stopping at the posts or removing the brushes off of contact in passing the posts

A roll for forming link blanks has been patented by Mr Jesse T Wright of New Albany, Ind. The curved ends of blanks to be subsequently punched are made on the last pass when rolling the bar to prepare for the blanks in deep, narrow grooves of the rolls, for passing the bar edgewise, with dies corresponding to the length of the blanks, and for shaping the ends separating the blanks for car coupling links.

A measure for grain, shot, and other like articles has been patented by Mr. Hiram W. White, of Yankton, Dakota Ter. This invention covers a special construction and arrangement of parts, bins with hopper shaped bottoms, having lozenge shaped apertures, a measure, with novel means for operating the slides to convey the material from the bins to the discharge chamber, and other peculiar features.

An improvement in the manufacture of bichromate of soda has been patented by Mr. William Simon, of Baltimore, Md. It consists in evaporating the solution of neutral chromate of soda to dryness before adding the sulphuric or hydrochloric acid, and adding to the dry salt common sulphuric acid, whereby anhydrous sodium sulphate crystallizes out, whence the concentrated solution of bichromate of soda is mechanically separated.

NEW BOOKS AND PUBLICATIONS.

TRAITÉ PRATIQUE D'ELECTRICITÉ INDUSTRIELLE. Par E. Cadiat et L. Dubost.

This work, as its title indicates, is a practical treatise on the subject of electricity and it has been the purpose of the authors to present the subject in a form as free from technicalities and abstruse mathematical calculations as possible, and to render it at once interesting and instructive and a ready work of reference to the artisan, the engineer, and mechanic. The first part of the treatise is devoted to definitions and fundamental laws as well as the most important subject of units and measures. Then follows an examination of the different kinds of batteries, dynamos, and electric generators, secondary batteries, etc. The third section contains a review of the various systems of electric lighting, also a comparison between the cost of lighting by electricity and gas and the application of the former to the illumination of ships, theaters, studios, shops, and residences. Electricity as a motive force as applied to railways and aerial navigation is treated of in part four. There are two other sections, which are devoted to galvanoplastic and electro metallurgy and telephony. This work of 500 pages contains numerous illustrations. Price 15 francs. Publisher, J. Baudry, 15 Rue des Saints Pères, Paris, France.

Business and Personal.

The Charge for Insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

Hearing Restored. A great invention by one who was deaf for 20 years. Send for particulars to John Garmore, Cincinnati, Ohio.

It gives us pleasure to say that the Remington No. 2 Type-writers which have been in use in this office are giving the best satisfaction. We like them better than any machines of the kind that we have ever seen.
BURNHAM, PARRY WILLIAMS & Co.,
Baldwin Locomotive Works. Philadelphia, Pa.

The Remington Type-writer is the one used by the United States Government. Wyckoff, Seamans & Benedict, 281 and 283 Broadway, New York city, sole agents.

Linen Safety Hose, all sizes, at greatly reduced prices. Greene, Tweed & Co., New York.

Experimental Machinery Perfected, models, patterns, etc. Tolhurst Machine Works, Troy, N. Y.

Catalogue of Books, 128 pages, for Engineers and Electricians, sent free. E. & F. N. Spon, 35 Murray Street, N. Y.

Wanted.—To correspond with works, corporations and cities desiring first-class, and at the same time low cost, electric light plants, with or without engines and boilers. "S. C. Forsaith Machine Company, Manchester, N. H."

Brush Electric Arc Lights and Storage Batteries. Twenty thousand Arc Lights already sold. Our largest machine gives 65 Arc Lights with 45 horse power. Our Storage Battery is the only practical one in the market. Brush Electric Co., Cleveland, O.

Practical Instruction in Steam Engineering, and situations furnished. Send for pamphlets. National Institute, 70 and 72 West 23d St., N. Y.

The Cyclone Steam Flue Cleaner on 30 days' trial to reliable parties. Crescent Mfg. Co., Cleveland, O.

For Steam and Power Pumping Machinery of Single and Duplex Pattern, embracing boiler feed, fire and low pressure pumps, independent condensing outfits, vacuum, hydraulic, artesian, and deep well pumps, air compressors, address Geo. F. Blake Mfg. Co., 44 Washington St., Boston; 97 Liberty St., N Y. Send for Catalogue.

Quinn's device for stopping leaks in boiler tubes. Address S. M. Co., South Newmarket, N. H.

Mills, Engines, and Boilers for all purposes and of every description. Send for circulars. Newell Universal Mill Co., 10 Barclay Street, N. Y.

Wanted.—Patented articles or machinery to manufacture and introduce. Lexington Mfg. Co., Lexington, Ky.

"How to Keep Boilers Clean." Book sent *free* by James F. Hotchkiss, 86 John St., New York.

Stationary, Marine, Portable, and Locomotive Boilers a specialty. Lake Erie Boiler Works, Buffalo, N. Y.

Presses & Dies. Ferracute Mach. Co., Bridgeton, N. J.

For Power & Economy, Alcott's Turbine, Mt. Holly, N. J.

The Hyatt filters and methods guaranteed to render all kinds of turbid water pure and sparkling, at economical cost. The Newark Filtering Co., Newark, N. J.

Steam Boilers, Rotary Bleachers, Wrought Iron Turn Tables, Plate Iron Work. Tippett & Wood, Easton, Pa.

Send for Monthly Machinery List
to the George Place Machinery Company,
121 Chambers and 103 Reade Streets, New York.

Walrus and Sea Lion Leather for polishing all kinds of metal. Greene, Tweed & Co., New York.

Iron Planer, Lathe, Drill, and other machine tools of modern design. New Haven Mfg. Co., New Haven, Conn.

If an invention has not been patented in the United States for more than one year, it may still be patented in Canada. Cost for Canadian patent, $40. Various other foreign patents may also be obtained. For instructions address Munn & Co., SCIENTIFIC AMERICAN Patent agency, 361 Broadway, New York.

Guild & Garrison's Steam Pump Works, Brooklyn, N. Y. Steam Pumping Machinery of every description. Send for catalogue.

Nickel Plating.—Sole manufacturers cast nickel anodes, pure nickel salts, polishing compositions, etc. Complete outfit for plating, etc. Hanson & Van Winkle, Newark, N. J., and 92 and 94 Liberty St., New York.

Supplement Catalogue.—Persons in pursuit of information on any special engineering, mechanical, or scientific subject, can have catalogue of contents of the SCIENTIFIC AMERICAN SUPPLEMENT sent to them free. The SUPPLEMENT contains lengthy articles embracing the whole range of engineering, mechanics, and physical science. Address Munn & Co., Publishers, New York.

Machinery for Light Manufacturing, on hand and built to order. E. E. Garvin & Co., 139 Center St., N. Y.

Munson's Improved Portable Mills, Utica, N. Y.

Mineral Lands Prospected, Artesian Wells Bored, by Pa. Diamond Drill Co. Box 423. Pottsville, Pa. See p. 332.

C. B. Rogers & Co., Norwich, Conn., Wood Working Machinery of every kind. See adv., page 350.

We are sole manufacturers of the Fibrous Asbestos Removable Pipe and Boiler Coverings. We make pure asbestos goods of all kinds. The Chalmers-Spence Co., 419 East 8th Street, New York.

Clark's Rubber Wheels. See adv. next issue.

Curtis Pressure Regulator and Steam Trap. See p. 286.

Steam Hammers, Improved Hydraulic Jacks, and Tube Expanders. R. Dudgeon, 24 Columbia St., New York.

Emerson's 1884 Book of Saws. New matter. 75,000. Free. Emerson, Smith & Co., Limited, Beaver Falls, Pa.

Hoisting Engines. Friction Clutch Pulleys, Cut-off Couplings. D. Frisbie & Co., Philadelphia, Pa.

Barrel, Keg, Hogshead, Stave Mach'y. See adv. p. 302.

U. S Standard Thread Cutting Lathe Tool. Pratt & Whitney Co., Hartford, Conn.

For best low price Planer and Matcher, and latest improved Sash, Door, and Blind Machinery, Send for catalogue to Rowley & Hermance, Williamsport, Pa.

The Porter-Allen High Speed Steam Engine. Southwark Foundry & Mach. Co., 430 Washington Ave., Phil. Pa.

Woodwork'g Mach'y. Rollstone Mach. Co. Adv., p. 286.

Split Pulleys at low prices, and of same strength and appearance as Whole Pulleys. Yocom & Son's Shafting Works, Drinker St., Philadelphia, Pa.

Notes & Queries

HINTS TO CORRESPONDENTS.

Name and Address must accompany all letters, or no attention will be paid thereto. This is for our information, and not for publication.
References to former articles or answers should give date of paper and page or number of question.
Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all, either by letter or in this department, each must take his turn.
Special Information requests on matters of personal rather than general interest, and requests for **Prompt Answers by Letter**, should be accompanied with remittance of $1 to $5, according to the subject, as we cannot be expected to perform such service without remuneration.
Scientific American Supplements referred to may be had at the office. Price 10 cents each.
Minerals sent for examination should be distinctly marked or labeled.

(1) J. T. W. writes: In the issue of October 25th, W. G. F. asks how calcium sulphide is used to remove hair, etc. Now, will calcium sulphide effectually and permanently remove superfluous hair, and if so, which of the sulphides of calcium? A The calcium and barium sulphides are considered effectual depilatories. The particular one that is used is the CaH_2S_2 or CaS,H_2S, called by Watts the sulphydrate of calcium.

(2) C. J. D. asks: Is celluloid used to coat metals, as is nickel? Can you give me a good solution to coat tin with to prevent acids from eating same? A. Celluloid is soluble in chloroform, and by painting the surface with such a solution, as the chloroform evaporates a coating of celluloid will be deposited. A coat of good hard drying asphaltic varnish would, we think, be more suited to your wants.

(3) H. A. D. asks for the formula for making a fluid substitute for silver plating which will last for a few days. A. Prepare a solution of one part potassium cyanide in 6 parts water; add to it a concentrated aqueous solution of silver nitrate (free from acid) until the precipitate is redissolved. Mix this solution with fine chalk, and apply after previously clearing the objects.

(4) E. B. B. asks how to extract the oil from the skins of duck or other water fowl, to be used for trimmings. A. Dip the feathers for a few minutes in coal tar naphtha or benzine, and then dry by exposing to the sun.

(5) V. J. P. asks if there is any way to hold sulphur in solution in mineral oil (paraffine) to be used as a lubricator. A. Sulphur is frequently a constituent of crude petroleum; it is soluble generally in the fatty oils, in naphtha especially, when the liquids are hot.

(6) E. S. B. writes: In a late number you say 1 ounce of salicylic acid will prevent fermentation in cider. Is this acid injurious to health? Would it not be a good ingredient in the composition of brine for the preservation of meat, making it unnecessary to use so much salt to make it keep? A. It is used as suggested by you for the preservation of meat. See SCIENTIFIC AMERICAN SUPPLEMENT, No. 226, for exact quantities to be employed. By some its use is condemned, while others assert that it is not at all injurious to the health.

(7) P. S. M. asks the average amount of square plate or pipe surface used in practice for heating 1,000 cubic feet of room space in buildings by hot water or low pressure steam, say 5 pounds, and the same for high pressure steam. A. 10 to 12 square feet per 1,000 cubic feet for hot water, 7 to 9 square feet per 1,000 cubic feet for low pressure according to exposure, and 6 to 7 square feet per 1,000 cubic feet for high pressure.

(8) G. C. G. asks a good receipt for preparing raw meerschaum for smoking purposes. A. When freshly exhumed the mineral is covered with red, oily earth, and is so soft as to be easily cut by a knife. Its preparation is slow and troublesome. After removal of the earth, it is dried 5 or 6 days in the sun or 8 to 10 in a hot chamber, then it is cleaned again and polished with wax. Then the different kinds, of which there are ten, are sorted and carefully packed with wood in boxes. In Germany, where the bowls of the pipes are principally exported to, they are prepared for sale by soaking them first in tallow, then in wax, and finally by polishing them with a sharc glass.

(9) J. C. A. writes: Can you give me a formula for an ink which after being printed on paper the print can be transferred to cloth by a warm flat iron, the ink not to crack when the paper (printed on) is folded or rolled up? A. The process you desire has been described as follows: Dust over the stencil white lead (or any suitable coloring material) with a little resin, fixing the pattern by covering with a piece of paper and ironing with a hot iron. When the cloth can be turned (as by placing between boards or book covers) without scattering the powder, it may be preferable to apply the heat directly to the back of the fabric. It is also possible to prepare an ink by dissolving the coloring material and adding a thin solution of mucilage of gum acacia. The mixture should have the consistency of thin paste.

(10) B. F. A. asks: 1. I have a casting 8 inches in diameter, how much sulphuric acid is required to make it 2 pounds lighter, and how strong should the pickle be? A. Castings are generally turned smaller by cutting away a certain amount on the lathe. From the data furnished no estimate could be given. 2. What is the composition of inclosed mineral, and what acid will take the rock off without injuring the diamond? It is found in hard coal mines. A. The specimen is iron pyrites, or sulphide of iron. Mechanical treatment will remove the coal; possibly a gentle heat might be used to burn away the coal. Acids would decompose the mineral, and would be without influence upon the matrix.

© 1884 SCIENTIFIC AMERICAN, INC

(11) E. E. S. writes: I desire to construct a small electric engine, with power enough to run a sewing machine or such other machinery of about the same size. Can you tell me where I can get a description or directions for so doing? A. There is little difference between a small dynamo electric machine and an electric motor. By following the instructions given in SUPPLEMENT, No. 161, for the construction of a small dynamo, you will be able to make a machine that will answer as a motor, by altering the adjustment of the commutator.

(12) W. A. M. asks how to make yeast cakes known as dry hop yeast and used for raising dough for bread. A. Marion Harland gives the following: 2 quarts water cold, 1 quart pared and sliced potatoes, double handful hops, tied in a coarse bag, flour to make stiff batter, and 1 cup Indian meal. Boil the potatoes and hop bag in two quarts of water for three-quarters of an hour. Remove the hops, and while boiling hot, strain the potatoes and water through a cullender into a bowl. Stir into the scalding liquor enough flour to make a stiff batter. Beat all up well, add two tablespoonfuls lively yeast, and set in a warm place to rise. When light, stir in a cup of Indian meal, roll into a sheet a quarter of an inch thick and cut into round cakes. Dry them in the hot sun or in a very moderate oven, taking care they do not heat to caking. When entirely dry and cold, hang them up in a bag in a cool dry place.

(13) W. F. S.—Perhaps the best method of preventing frost from forming on window glass is to cover the glass with a thin film of glycerine.

(14) A. De W. asks (1) if there is anything to bleach vaseline to a pure white or lard color. A. According to the U. S. Dispensatory, vaseline or petrolatum is decolorized by passing it through charcoal when in a liquid condition. 2. What is the best thing to remove paint and grease spots out of last year's overcoat without spoiling the goods? A. For the cleansing of various fabrics see table given in SCIENTIFIC AMERICAN SUPPLEMENT, No. 158.

(15) J. M. P.—Receipts for burnishing ink for shoes are numerous, but all the successful makers of this article have secrets, either as to the ingredients or the method of manufacture, which they guard as a valuable property right. As pertinent to this subject, we have knowledge of an attempt by a New York dealer to make an ink similar to that furnished by a leading Eastern manufacturer, in which the New York dealer failed after expending more than $10,000 in his experiment.

(16) J. S. O'B.—The American Bell Telephone Company claim to control all speaking telephones. If they are able to sustain their claim, you will, of course, not be entitled to make the telephone referred to for your own use or for any other purpose. The telephone described in SUPPLEMENT, No. 142, if well made, will talk for five or six miles. You should not use smaller than No. 14 iron wire; the No. 12 is the size commonly used. A magneto call bell is generally used with this kind of telephone. You can get a good ground connection by attaching your wires to the water pipes or to plates of copper, each having an area of about 8 or 10 feet, buried in earth that is constantly moist.

(17) F. U. S. writes: I have some fine colored engravings which have been badly soiled with printer's ink. Can you inform me what will remove the same without defacing the pictures? A. The process of cleaning soiled engravings is described in SCIENTIFIC AMERICAN SUPPLEMENT, No. 44. It would apply also to printer's ink, but the process is a delicate one, and great care must be taken not to injure the engraving Hydrogen peroxide is another excellent bleaching agent.

(18) J. H. M.—As a young man desiring to become a thorough electrician, we think your better way would be to secure employment in some establishment manufacturing electrical apparatus, and while thus engaged to study the subject of electricity. You might begin with Sprague's new work on electricity, then study the works of Gordon and others on electric lighting and the general applications of electricity.

(19) D. W. asks how the polish is put on playing cards. A. All the successful manufacturers have some secrets in this department of their business, but the polish is made by a coating of size or varnish and then passing the sheets, with metal plates, through polishing rollers.

(20) D. E. C.—Lacquer for tin: Brass color: 3 ounces seed lac, 2 drachms dragon's blood, 1 ounce turmeric powder, 1 quart 95 per cent alcohol or methylic alcohol; put in a bottle well corked, and place in a warm place and shake up occasionally for a week or ten days, then strain through a fine cloth. Temper with methylic alcohol so as to spread freely with a brush. Heat the tin in an oven about as hot as boiling water: brush the lacquer on quickly. Vary the dragon's blood and turmeric to suit your taste as to depth of color.

(21) J. M F.—Lime cylinders for calcium lights are commonly made from selected pieces of unslaked lime of good quality. They are also made of lime obtained by calcining marble. We know of no method of utilizing slaked lime in a calciumlight.

(22) F. B.—Leclanche battery is good for certain kinds of experiments. It will not yield a constant current for a very long time; it certainly is cheap and clean, and if you require a current intermittently for a few moments at a time, it will probably answer your purpose. If you want a continuous current, the Daniell or the gravity battery would be better for your purpose.

(23) A. F. L. asks the cheapest and most practical way to finish cheap soft wood furniture, and what ingredients are used for such finishing. A. Fill the pores of the wood with a Wheeler wood filler, then apply one or two coats of white shellac varnish.

(24) J. C.—The process of separating fiber from vegetable growth depends something on the kind of fiber and the kind of vegetable from which it is to be separated. In general the vegetable may be reduced to a pulp by rolling or pounding, and then it may be washed away from the fiber. There are machines in use for this purpose, and a number of them have been patented. We know of no process of making the fiber stronger than it is, after being thoroughly freed from the vegetable pulp.

(25) J. F. D.—The great proportion of the carriage hardware used now is made of malleable iron, generally cast in one piece. Some of the better kinds of carriage hardware are made by the process of drop forging. The machinery used for producing such forges is a drop press and a steam or drip hammer.

(26) E. L. K. writes: I have an oscillating engine cylinder 1¼ diameter, 2 inches stroke. Have got to make a boiler. Have got a 3 burner oil stove, and am going to make boiler all of copper, and following dimensions to fit it: Drum 6 inches diameter, 6 inches long, shell one-sixteenth inch thick, heads a quarter of an inch thick, 40 drop tubes three-quarters of an inch diameter outside, 6 inches long, one-sixteenth thick, 1 tube passing through drum as flue in center for stay. This will be well jacketed. Would like to know how much pressure is safe to carry, and if of sufficient capacity for above engine, understanding of course that boiler is to be well made. A. We doubt the propriety of putting 40 tubes ¾ inch in a 6 inch head. If the heads are slightly raised and the tubes made radial, you will add to its efficiency; one tube through center will not be sufficient vent. Such a boiler, if properly made with well brazed joints, ought to carry 80 pounds pressure and of capacity equal to your engine.

(27) H. M. F. asks (1) the size and kind of wire to make a spark coil for lighting gas. A. You will find instructions for making induction coils in SUPPLEMENT, No. 160. A simple magnetic coil of eight or ten layers of No. 18 or 20 wire will answer for gas lighting purposes. 2. How many cells of Faure's secondary battery would it take to light an incandescent light to read by, the secondary cells to be charged by one of Edison's large dynamos? How long would it take to charge them, and how long would they last? A. There is no economy in operating a single incandescent lamp by means of a secondary battery or in any other manner. A sixteen candle power incandescent lamp will probably require from 15 to 20 cells of secondary battery. To charge a secondary battery economically should take several hours, and the length of time during which the battery will yield a current depends altogether upon the resistance of the circuit through which it has to work. If the resistance is high, the battery will work for several hours; if the resistance is very low, the battery will run down in a few minutes.

(28) J. H. C. asks: 1. Is there an established rule for the speed of the circumference of the paddle wheels of a steamboat to give best results? A. No. 2. What length should the paddles be in proportion to width of boat? A. Usually about one-third, but depends much on model and draught of water. 3. Would a one horse engine run a boat capable of carrying a ton, the boat of fair proportion, and at about what speed? A. It would run a boat with speed, but little if any better than with two pairs of oars. 4. What length and width of boat—not to draw more than eight inches—would it require to carry 2,500 pounds? A. Depends much on model and weight of boat; if model is sharp, boat not less than 34 feet long and 6½ feet beam.

(29) E. L. S. asks: 1. What per cent of the power required to run a dynamo machine is utilized by the best motors in use, if they should receive the current from the dynamo? A. About sixty per cent. 2. Where can I buy a small dynamo of sufficient power to give electrical shocks? A. From any of the dealers in electric supplies who advertise in our columns. 3. About what is the electro-motive force of a small Grenet battery in good order in volts? A. About 1½ volts.

(30) C. G. S. writes: I have dipped my pencil into a goblet, and brought up a drop of water. 1. What force binds together the pencil and the drop? A. The attraction of adhesion. 2. What holds the drop to other drops? A. Cohesion. 3. Why is not this ice instead of water? A. Because it is fluid. 4. If I shake the pencil, in what direction does the drop fall? A. In a tangent to the line followed by the point of the pencil. 5. If the drop were larger than the world, which way would the world go? A. It might follow the drop of water. 6 What other force is there in it which, according to Faraday, is equal to that in a flash of lightning? Here are, then, five great forces in a drop of water. What I wish to know is the name of those forces, as cohesion, gravity, etc.? A. If furnished with the proper accessories, it might generate an electric current, which would equal in quantity the quantity of a very small flash of lightning.

(31) H. B. asks the size of boiler to give the best results in working a ten horse power engine (vertical), and says he will also require two horse power of live steam for other uses. A. If for anthracite coal, 32 or 34 inches diameter of shell and 11 feet in length; 20 or 22 return tubes 3 inches diameter. If bituminous coal be used, it would be best to make the boiler 18 inches or 2 feet longer. This boiler should supply the power with small grate, and economically.

(32) H. B. M.—We understand the engines referred to, to be the same which have so often broken down. You can rely upon it, that there is to be no gain of 30 per cent by the "patent quadrant."

(33) W. H. M. asks for the length and original cost of steamers Bristol and Providence, plying between Fall River and New York? A. Three hundred and sixty-two feet long; original cost understood to be about $900,000 each.

(34) F. W. writes: 1. Will you instruct me how to build a Holtz electric machine? A. Consult SUPPLEMENT, 278, 279, and 282. 2. Is hard rubber or glass preferable? A. Use common window glass. 3. What is the price of hard rubber in sheets? A. We believe it is about a dollar a pound. 4. Does the machine work equally as well in damp as in dry weather, or does moisture in the air affect it, as is the case with the old time electric machine with glass disk and rubbers? A. It will work better than the old fashioned disk and rubber, but it will sometimes fail in very warm damp days. 5. Will size of spark be increased by increasing size of plates? A. The size of a spark will be increased by increasing the size of the Leyden jars attached to the machine. The length of the spark will be increased by using plates of larger diameter. 6. Would it be possible to utilize the spark for illuminating purposes, and if not, why? A. No. The current generated by the Holtz machine has a very high intensity, whereas a quantity current is required for illumination.

(35) N. E. F. writes: If a man makes an improvement on the Bell telephone that does not infringe their patents, has he a right to attach it to an instrument he has rented of them, and use it for his own use? A. We know of nothing to prevent you from applying and using your improvement.

(36) C. M. writes: I have modeled flowers in clay, and would like to know how to bake them so that I can paint them. What else would answer the same purpose as clay? A. The method of baking the flowers you have modeled in clay depends in a measure upon the character of the clay, and we know of no way to determine the best method without experiment. A mixture of glue, resin, and whiting is used for the ornaments of gilt frames, and it might possibly answer your purpose. It is moulded warm, and, of course, needs no baking.

(37) W. B. R. asks of what agate buttons are made? A. Genuine agate buttons are, of course, made from natural agates; the artificial article is made of colored glass.

(38) W. M. B. writes: I desire to sustain a weight, say 2,500 pounds, on two floats, 24 feet apart; the weight must be 4 feet from one and 20 feet from the other float. I know the total displacement will be approximately 40¾ cubic feet; how much displacement will there be in the large float, four feet from the weight, and how much in the small float, twenty feet from the weight? I think approximately 32 cubic feet in the large float and 8 feet in the small float. A. Your figures are correct for the centers of floats from supporting fulcrum. This is without consideration of the weight of the material of the floats and balance beam. The floats must be as much larger than your figures as is equivalent to the weight of the apparatus, in order to be equal to the support of 2,500 lb.

(39) J. T. writes: I use a good deal of walrus tusk for handles, and very often they have a yellow stain in them. I used to bleach them in the sun, but it is a very slow process. Is there any quicker way? A. Elephant tusks are bleached in three or four days by immersion in turpentine, keeping near the surface, and exposing to sunlight, and probably this is the best way now known for your purpos.

(40) G. W. B. asks: 1. What kind of cement used, and how to cement gum face on band saws? A. Ordinary rubber cement, such as you can purchase at any of the rubber stores, will answer your purpose. 2. Is there anything to be put in glue to prevent moisture from disturbing the joints in patterns? A. A little bichromate of potash put into your glue will render it insoluble, after exposure to light. 3. Is there anything to prevent shellac used for patterns from getting dark before using after it is mixed some time? A. We know of no way to prevent this.

(41) A. C. H. asks by what mode or process the rust stains in old Leclanche porous cups can be removed? A. Try dilute sulphuric acid.

(42) E. L. H. asks is there any way or process to reharden annealed brass rods? A. We know of none, except redrawing or burnishing, which will only harden the surface.

(43) S. E. F.—Waxed paper, such as used for wrapping soap, is prepared by placing cartridge or other paper on a hot iron and rubbing with beeswax or brushing on a solution of wax in turpentine. On a large scale, it is prepared by opening a quire of paper flat upon a table, and rapidly ironing it with a very hot iron against which is held a piece of wax, which, melting, runs down upon the paper and is absorbed by it. Any excess on the topmost layer readily penetrates to the lower ones.

(44) W. S. C.—In closed circuits for steam heating, the pressure of the steam along the flow pipes and in coils in well arranged systems is so nearly equalized with the pressure in the boiler, that it requires but small elevation of the water of condensation in the return pipe above the water level in the boiler to allow of its return by gravity. In this system all of the radiators should be not less than from 1 to 5 feet above the water level in the boiler, according to the complication and extent of the circuit. The air is discharged at the radiators, and no waste of water is necessary.

(45) W. B. R. writes: I have about a ton of tacks slightly rusted. How can I clean them? Sulphuric acid does it, but they rust again before I can dry them. Attrition in a rattler ruins the points. If dried in sawdust, how can I separate them from the same? If with lime, how remove that? They must be clean enough to carry in the mouth, as is the practice of most users of tacks? A. Put the tacks in a wire cloth basket, dip in the sulphuric acid bath and quickly plunge in boiling hot water, then in boiling hot lime water, then throw the tacks upon a wire cloth over a fire to dry quickly. The lime water should only contain as much lime as the water will hold in solution cold. It should not be milky.

(46) Dr. E. H.—Remove your carbon electrodes from the porous cells of your battery, and soak them for a day in warm water. Remove the granulated black oxide of manganese from the cells, and soak the cells in warm water for the same period; then replace the carbon electrodes in the cells, and fill with fresh granulated black oxide of manganese, and seal the cells with pitch, leaving a small aperture in the sealing for the escape of air, and we think you will find your batteries as good as new.

(47) G. D. writes: 1. Can you give formula for gelatine pads and the ink for use with them? A. consult article on "New Copying Process" in SUPPLEMENT 374. 2. I wish to light with bichromate batteries, using at different times 2, 5, and 10 Edison lamps. How many cells will I require in each case, and how should they be connected—for quantity or intensity? A. We cannot advise you to attempt to operate ten Edison lamps with bichromate batteries. You will find it exceedingly troublesome and expensive. You can light one or two for experimental purposes readily enough, but if you desire to run ten lamps for actual use, we advise you to purchase a dynamo and a steam engine to generate the current. If you conclude to try the experiment of lighting by means of incandescent lamps, operated by batteries, you might begin with about 150 cells of carbon bichromate battery of the Bunsen type. The lamps should be connected in multiple arc and the batteries in series of two to four, and these series connected for quantity.

(48) G. H. P. writes: I have a turbine water wheel which I am running with a full gate, using it to drive a paper machine. I am told, if I put on a larger driving pulley, that I will then drive the machinery faster with the same power. I contend that this cannot be so. A. Our opinion is that you cannot gain power by enlarging the pulley unless you can raise the head of water; much depends upon the present speed and size of wheel. The opinion of the maker of the wheel will be more reliable than that of those not knowing the peculiarities of its construction. If the wheel is now running at a very high speed, the reaction may not be perfect; in such case, increasing the size of the pulley might be of benefit. Our reference to the maker is therefore the best advice.

(49) W. A. M.—Good glue mixed with about one-quarter its bulk of fine wood ashes makes a strong cement impervious to oil. Gutta percha dissolved in bisulphide of carbon makes a strong cement not easily penetrated by oil. Make the cement as thick as treacle. Warm the parts to be cemented, and press together tightly.

(50) W. O. McK.—The Scotch water gauge glasses are made of silica and kelp or potash, and are slightly soluble, especially in acid waters, in which we understand, your State abounds, as we frequently hear of its action upon boiler tubes and pipes. Its action is more marked where there is rapid circulation. If you will measure accurately the inside of a new glass tube, and make comparison after a few months' use, you will probably find the hole larger by the dissolving or wearing away of the interior, as well as the exposed end.

(51) W. S. P. asks: What is a solar compass? On what principle it works? A. The solar attachment is a frame with arms and graduated limb, placed upon the telescope of a compass or field transit for the purpose of obtaining local meridians by observation of the sun's position. We cannot give a detailed description that you can comprehend without illustrations.

(52) M. R. S.—The crystallizing barometer or weather glass should not have a closed tube or be hermetically sealed, but should have an open top covered with gold beater's skin or fish bladder so loosely that the difference of pressure of the air may be transmitted to the liquid within the glass, otherwise it is of no value whatever. The alcohol holding camphor in a saturated solution crystallizes variably with the pressure, and does not always rise and fall, contrary to the motions of the mercury barometer, but often in the most fantastic combinations. It is a pretty and curious instrument for the study of the formation of crystalline combinations, but useless as an instrument of precision.

(53) W. M. J. M. asks: Would it be advisable in building a small steam yacht with a high pressure engine to put the exhaust under the fan tail and under water, to prevent the noise? A. The exhaust may be carried through the bottom and alongside of the keel, opening under the screw. It will partly condense in the pipes, and makes a little noise by concussion with the water. We do not think it of much advantage. Making the upper part of the exhaust pipe two or three times larger than at the engine, will modify its intensity.

(54) S. R. L. asks for receipts for dyeing cotton fabric red, blue, and ecru. A. Red: Muriate of tin, two-thirds cupful, add water to cover goods; raise to boiling heat; put in goods one hour; stir often; take out, empty kettle, put in clean water with Nicaragua wood one pound; steep one-half hour at hand heat, then put in goods and increase heat one hour, not boiling. Air goods, and dip one hour as before. Wash without soap. Blue: For three pounds goods blue vitriol 4 ounces, boil few minutes, then dip goods three hours; then pass them through strong lime water. Ecru: Continue the foregoing operation for blue by passing the goods through a solution of prussiate of potash. Also see the receipts given in SCIENTIFIC AMERICAN SUPPLEMENT, No. 167.

(55) E. H. S.—Coal tar alone with gravel and sand for side walks does not dry well. Asphaltum with equal parts of coal tar melted together and sprinkled upon the mixed sand and gravel that has been made hot upon an iron plate (the mixing to be done in a large pan of iron), putting no more asphalt and tar upon the sand and gravel than will just make it stick together; then dump into place while hot, spread quickly, and beat level with a ram or heavy roller. Dust over the surface with fine sand before rolling or beating, to prevent the material from sticking to the roller or beater. This operation requires a little care and experience as to just the amount of asphalt and tar for a given measure of sand and gravel, and also for the proportions of sand and gravel required to make the best pavement. Sometimes a thin bed of broken stone is laid as a foundation. Also a thin bed of coarse gravel is sometimes spread before dumping the hot mixture.

© 1884 SCIENTIFIC AMERICAN, INC

(56) J. F. S. writes: Can you inform us as to preparation or manufacture of "oil of apple" or "essence of apple," advertised by manufacturers and dealers in oils, extracts, essences, etc.? A. The essence of apple is composed of aldehyde 2 parts; chloroform, acetic ether, nitrous ether, and oxalic acid each, 1 part; glycerin 4 parts; amyl valerianic ether 10 parts. 2. Please give a formula for the manufacture of artificial cider. A. Imitation cider consists of 25 gallons soft water, 25 pounds New Orleans sugar; 1 pint yeast; 2 pounds tartaric acid. Put all the ingredients into a clean cask, and stir them up well after standing twenty-four hours with the bung out. Then bung the cask up tight, add 3 gallons spirits, and let it stand 48 hours, after which time it will be ready for use. 3. And champagne cider. A. Champagne cider can be prepared by taking 10 gallons of cider, old and clear. Put this in a strong iron bound cask pitched inside (like beer casks); add 2½ pints clarified white plain sirup; then dissolve in it 5 ounces tartaric acid; keep the bung ready in hand, then add 7½ ounces of potassium bicarbonate; bung it as quickly and as well as possible.

(57) A. H. says a manufacturer of ladders here contends that ladder rounds (for a common straight ladder) tapered off from the center gradually to the ends down to the size of the tenons are stronger and stiffer than to leave the rounds straight and taper them off at the ends just enough for the tenons; rounds the same size in the center. Is he right? A. No. He is wrong.

(58) S. Van D. asks: Why does a sulphurous smell always accompany a thunderbolt? A. The odor is supposed to be due to the formation of ozone.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted

November 25, 1884,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Acid, making hydrochloric, L. Mond 308,511
Adding machine, Noyes & Stark 308,570
Adding machine, A. Stark 308,528
Advertising device, J. C. Blevney 308,339
Amalgamator, M. T. Van Derveer 308,584
Anchor support and tripper, R. P. Trefry 308,446
Auger, post hole, G. W. Gilmour 308,354
Axle box, car, G. W. Sweeney 308,579
Axle, vehicle, J. O. Therien 308,531
Bag and pouch fastening device, J. Fickinger 308,350
Belt guide, J. E. Laying 308,417
Belt shifter or stop motion, H. A. Green 308,357
Bench and stand, combined, J. W. Walters 308,538
Berth, automatic ship's, W. T. Milligan 308,423
Bicycle, Stillwell & McNab 308,442
Blotter, N. O. Pyles 308,378
Blotting thimble or pad, A. B. Bromwell 308,462
Boneblack drier, E. P. Eastwick 308,475
Boneblack kiln, E. P. Eastwick 308,476
Book support, adjustable, W. O. Johnson 308,499
Bottle filling device, G. A. Kintz 308,364
Bottle wrappers, material for, S. Friend 308,352
Brake. See Lathe friction brake.
Brake shoe, D. Prew 308,430
Brick for regenerative furnaces, S. A. Richards 308,577
Brick kiln, J. Weaver 308,391
Bridge, M. Kersten 308,501
Broom, P. A. Yoergensen 308,396
Broom shield, Dew & Robertson 308,470
Brush, B. Normandin 308,427
Brush, blacking, Eaton & Fenn 308,477
Brush, stove, C. Barrett 308,338
Buckle, trace, J. O'Brien 308,515
Burglar trap, G. Grebe 308,488
Butter worker, M. D. Woodbury 308,395
Button, T. W. F. Smitten 308,441
Camera. See Photographic camera.
Can. See Oil can.
Cannon, manufacture of, B. T. Babbitt 308,399
Cant dog and pry, combined, A. K. Doe 308,471
Cant dog, pry, and pike, combined, A. K. Doe 308,472
Car coupling, P. Brown 308,404
Car coupling, J. D. Kiely 308,414
Car coupling, J. P. Lancaster 308,503
Car coupling, J. A. Reid 308,380
Car uncoupler, electro-magnetic, J. D. Reed 308,432
Carriage, child's, G. R. Clark 308,467
Carrier. See Cash carrier.
Cash carrier, C. Fisher 308,480
Caster, J. I. Duncan 308,474
Casting ingots of metal, apparatus for, Durfee & Egleston 308,405
Chair. See Folding chair.
Chuck, J. H. Westcott 308,541
Churning device, A. Cairns 308,463
Cigarette machine, W. H. Emery 308,556
Clock, electro-mechanical, C. H. Pond 308,521
Cock, stop, C. Pfaudler 308,519
Cocoa roaster, H. Stollwerck 308,529
Cooking and collecting the resulting gases and their products, apparatus for, T. Nicholson 308,514
Collar, horse, S. L. McClanahan 308,367
Confectionery, machine for making, P. A. Johns 308,412
Cork strip for protecting steam and gas pipes, etc., J. Bourdon 308,402
Corks, metallic cap for, A. L. Bernardin 308,458
Corset fastening, T. J. Wood 308,587
Cultivator, T. E. Gregg 308,490
Cultivator, W. B. Patterson 308,374
Cultivator attachment, F. Albrecht 308,455
Cutter. See Moulding cutter.
Dental tool, J. G. Morey 308,424
Derrick, T. Gaffney 308,486
Digger. See Potato digger.
Drier. See Boneblack drier.
Drill. See Rock drill. Stone drill.
Easel, T. C. Vail 308,535
Eccentric, variable, E. Py 308,377
Egg, fruit, and honey carrier, L. H. Taylor 308,530
Electric motor, Blodgett & Tierrell 308,548
Electric motor, G. Trouvé 308,534
Electricity gauge, J. & H. M. Goodman 308,487
Embalmer's and undertaker's cabinet, T. C. Quayle 308,431
Embroidery frame, I. Elder 308,406
Engine. See Gas engine.
Evaporator. See Sugar evaporator.
Eye bars, manufacture of, E. W. Eckert 308,348
Fastener, metallic, G. W. McGill 308,368
Faucet, compound, C. H. Waters 308,540
Faucet protector, ale, G. Hirschman 308,560
Feed lubricator, visible, T. Brabson 308,403
Feed water, heating, C. N. Petesch 308,376
Feed water regulator, E. D. Shepardson 308,387
Fence post, M. J. Schott 308,384
Fence wire, L. W. Lindley 308,505
Fence wire, barbed, Woodruff & Hutchins 308,451
Fertilizer, J. R. Young, Jr 308,397
Filter, A. D. Puffer 308,575
Filter, cooler, and refrigerator, combined, W. E. Templeton 308,580
Firearm, W. Newcomb 308,513
Firearm, breech-loading, W. & S. E. Folk 308,482
Fire escape, A. H. Terwilliger 308,444
Firplace, E. Chickering 308,465
Folding chair and bathtub, combined, S. J. & S. A. Beach 308,456
Frame. See Embroidery frame. Spectacle frame.
Frames, etc., manufacture of covered, D. & D. C. Wheeler 308,586
Furnace. See Gas furnace. Hot air furnace. Regenerator furnace.
Furnace crown bar, White & Hodgson 308,450
Furnace door, T. R. Butman ..... 308,550 to 308,552
Gauge. See Electricity gauge. Shingling gauge.
Garment fastener, A. V. Smith 308,439
Gas engine, B. Parker 308,572
Gas furnace for metallurgic purposes, T. G. Kirkpatrick 308,564
Gas furnace, natural, J. N. Pew 308,518
Generator. See Steam generator.
Glass cutting machine, P. C. Claflin 308,466
Governor, steam engine, A. L. Ide 308,498
Governor, steam engine, H. Whiting 308,392
Grain elevators, revolving chute for, J. Hughes 308,496
Grinding mill, roller, W. R. Fox 308,557
Gumming machine, Furnival & Daniels 308,353
Hand protector, M. Bidwell 308,459
Handle. See Pail handle.
Harmonium and piano, combined, L. Küstner 308,415
Harness, H. T. Fountain 308,485
Harrow, Hetrick & Stimmel 308,360
Harrow, W. W. Robinson 308,433
Hat holder, T. B. Boyd 308,342
Hay rake, horse, A. W. Stevenson 308,578
Heel counter machine, M. Hynes 308,497
Hinge, spring, J. H. Alexander 308,337
Hinge, spring, P. H. Walsh 308,537
Hoisting gear, W. W. Wythe 308,453
Hoisting machine, J. Boyd 308,340, 308,341
Holder. See Hat holder. Stencil holder. Tidy holder.
Horseshoe, W. V. Wallace 308,449
Hose reel, Harding & Hill 308,411
Hot air furnace, J. B. Oldershaw 308,428
Hydraulic motor, N. Yagn 308,544
Injector, steam boiler, F. B. Maxwell 308,507
Jars or cans, cap or cover for, T. G. & J. H. Otterson 308,571
Jewelry, ornamenting, C. J. Leyers 308,504
Joint. See Rail joint. Railway joint. Universal joint.
Kiln. See Boneblack kiln. Brick kiln.
Lace fastening, F. M. Munroe 308,569
Lantern, W. S. Tryon 308,581
Lasting machine, H. A. Smith 308,527
Lathe friction brake, U. & H. E. Eberhardt 308,347
Letter sheet and envelope, combination, D. W. Clegg 308,554
Letter sheet and envelope, combined reversible, D. W. Clegg 308,555
Leveling instrument, W. H. Munford 308,426
Lifting jack, J. S. Hood 308,361
Link blanks, roll for forming, J. T. Wright 308,452
Lock and latch, combined, H. L. Heaton 308,559
Loom for weaving hair cloth, Greenhalgh & Wadsworth 308,489
Loom stop mechanism, E. Herzig 308,359
Lubricator. See Feed lubricator.
Lubricator, L. B. Bailey 308,400
Malt husks, treating, P. Ammann 308,398
Measure for grain, shot, etc., H. W. White 308,542
Metals, process of and apparatus for the treatment of ores for the extraction and separation of their, J. J. Shedlock 308,439
Milk, apparatus for preserving, J. Meyenberg 308,421
Milk, preserving, J. Meyenberg 308,422
Mill. See Grinding mill. Roller mill.
Millstone driver, J. F. Callahan 308,464
Moulding cutter, J. Phillips 308,520
Motor. See Electric motor. Hydraulic motor. Spring motor.
Mouse trap, D. B. Wirt 308,394
Nailing machine, J. Nagle 308,370
Nut washer, W. A. Jordan 308,562
Oil and glue from bones, etc., extracting, F. Seltsam 308,436
Oil can, W. Snow 308,389
Ore concentrating apparatus, O. Hanson 308,410
Ores, apparatus for disintegrating, H. B. Meech 308,510
Packing, metallic, S. Armstrong 308,546
Pail handle, etc., S. C. Cary 308,343
Painting wire fences, apparatus for, Marsau & Hill 308,506
Paper-hanging device, G. W. Schock 308,382
Paper satchel, C. L. Lockwood 308,418
Paper sizing and drying machine, combined, L. A. Fernon 308,408
Pea and bean sheller, E. R. Young 308,589
Photographic camera, W. Clark 308,468, 308,469
Pianoforte attachment, E. Höfinghoff 308,495
Piano pedal key attachment, J. Shaw 308,386
Pills, machine for making, J. A. McFerran 308,508
Planter, J. B. Altman 308,545
Planter and cultivator, combined seed, T. B. Shannon 308,437
Plow, A. Schindler 308,383
Plow, M. M. Warmoth 308,539
Plows, tongue latch for wheel, R. Newton 308,371
Post. See Fence post.
Potato digger, C. A. Denison 308,346
Power by belts and pulleys, device for transmitting, N. Yagn 308,588
Preserving fruit, etc., apparatus for, W. A. Wicks 308,393
Protector. See Hand protector.
Pump, W. S. McLeod 308,509
Rail joint, D. E. Bishop 308,460
Railway appliances by electricity, apparatus for controlling, J. T. Hambay 308,494
Railway joint and chair, combined, L. Haas 308,491
Railway signals by electricity, apparatus for controlling, J. T. Hambay 308,492
Railway switch, G. W. Parsons 308,373
Railway switch circuit closer, J. T. Hambay 308,493
Railway switch locking device, T. Rowlands 308,434
Railway switch stand, A. Baker 308,401
Rake. See Hay rake.
Reel. See Hose reel.
Regenerator furnace for use of natural gas, T. G. Kirkpatrick 308,565
Regulator. See Feed water regulator. Watch regulator.
Roaster. See Cocoa roaster.
Rock drill, H. C. Sergeant ..... 308,523 to 308,525
Roller mill, Mumford & Moodie 308,568
Sash fastener, J. A. Paine 308,517
Saw, A. & C. W. Boynton 308,549
Scale, letter, J. E. Smith 308,440
Scraper, earth, C. E. Outhwaite 308,372
Seal and railway ticket for milk cans, G. W. Evans 308,478
Sewing machine, J. Tripp 308,390
Sewing machine shuttle, D. L. & W. H. Keeler 308,363
Sheet metal bending machine, O. A. Fairchild 308,349
Sheller. See Pea and bean sheller.
Shingling gauge, S. T. Poe 308,574
Ship's log, hydrostatic, A. Kurreick 308,502
Shoe, S. C. Crowe 308,345
Signaling apparatus, electro-mechanical, M. Toulmin 308,533
Silk goods, preparing trams for, R. Simon 308,526
Skate, roller, O. Arnold 308,547
Sled, hand, R. W. Williams 308,543
Soda water apparatus, W. H. Greene 308,558
Sodium bicarbonate, manufacture of, Mond & Jarmay 308,512
Sower, fertilizer, J. W. Watts 308,585
Spark arrester, C. Foster 308,484
Spark arrester, J. A. Jones 308,500
Spectacle frame, E. Collins 308,344
Spring. See Watch case spring.
Spring motor, A. Marques 308,419
Spur, J. Kaino 308,413
Staple, P. W. Doherty 308,473
Steam engine reversing gear, E. A. Marsh 308,567
Steam generator, O. D. Orvis 308,429
Steam generator, M. H. Smith 308,388
Steam pipe covering, J. M. Ordway 308,516
Stencil holder, J. W. Bennett 308,457
Stone dressing machines, rotary cutter head for, J. W. Maloy 308,366
Stone drill, T. M. Yerkes 308,454
Store service system, C. Fisher 308,481
Stove, vapor, W. E. Kauke 308,563
Strap attachment, B. F. Rice 308,581
Sugar evaporator, Ferguson & Post 308,407
Tag, J. F. Miller 308,369
Telephone and automatic fire alarm system, combined, T. D. Lockwood 308,566
Telephone, mechanical, I. F. Tucker 308,582
Tidy holder, F. F. Unckrich 308,583
Tile laying machine, Walls & Engle 308,586
Time detector, electric, A. Lasmoles 308,416
Time indicating apparatus, C. H. & C. W. Thompson 308,532
Tool for grasping and holding articles, J. Goodrich 308,356
Track fastener, J. Forshey 308,483
Tramway, overhead, R. Cartwright 308,553
Trap. See Burglar trap. Mouse trap.
Truck, hand, W. W. Hughes 308,362
Universal joint, R. H. Gleason 308,355
Upholstering purposes, machinery for curling fibers for, O. C. Flick 308,351
Valve, S. Bradbury, Jr 308,461
Valve, safety, Falk & Frazier 308,479
Valve with relief attachment for fountains or other vessels under pressure, draught, L. W. Puffer 308,576
Vapor burner, petroleum, W. H. Peck 308,573
Vessels, balancing device for, R. Schaum 308,435
Wagon, dumping, R. D. Shackleford 308,385
Washer. See Nut washer.
Watch case spring, C. W. Thiery 308,445
Watch regulator, G. I. Tuttle 308,448
Watch stem winding and setting mechanism, H. M. Haines 308,409
Water closet, F. B. Hanson 308,358
Whiffletree, spring, C. B. Morse 308,425
Wells and oil bearing rock and tube therefor, extracting oil from oil, W. Richards 308,522
Windmill, G. H. Pattison 308,375
Window bead fastener, E. W. Talbott 308,443
Wire, annealing, E. Tucker, Jr 308,447
Wire drawing apparatus, H. L. Rawson 308,379
Wrench, J. Houlehan 308,561

DESIGNS.

Basque, lady's, L. Tully 15,581
Carpet, N. Komori 15,572, 15,573
Cloak, miss', M. Kavanagh 15,574
Clock case, A. O. Jennings 15,571
Costume, girl's, J. Q. Reed 15,578
Costume, lady's, M. Turner 15,582
Costume, miss', S. J. Shiels 15,579
Rug, A. Petzold ..... 15,575 to 15,577
Type, printing, H. H. Thorp 15,580

TRADE MARKS.

Baking powders, Oriole Baking Powder Company 11,717
Baking powders, Queen City Chemical Company 11,719
Bitters, Picon & Co 11,718
Bitters, J. G. B. Siegert & Hijos 11,720
Blacking and preparations for polishing boots, E. Brown & Son 11,699, 11,700
Bustles, E. E. Hodson 11,707
Cigars, E. H. Gato 11,706
Coffee and spice mills, H. H. Coles 11,701
Flour, wheat, J. Boyd, Jr., & Co 11,698
Food for infants, Fairchild Bros. & Foster 11,704
Food for infants, milk, H. Nestle 11,710, 11,711
Medicines, certain named proprietary, Flower Medicine Company 11,705
Milk, condensed, H. Nestle 11,709
Oil made from petroleum, lubricating, W. H. Compton 11,702
Patterns and linings for ladies' dresses, Moschcowitz Bros 11,708
Pens, metallic, Esterbrook Steel Pen Manufacturing Company 11,703
Yarns, worsted and woolen, Nonantum Worsted Company ..... 11,712 to 11,716

A printed copy of the specification and drawing of any patent in the foregoing list, also of any patent issued since 1866, will be furnished from this office for 25 cents. In ordering please state the number and date of the patent desired, and remit to Munn & Co., 361 Broadway, New York. We also furnish copies of patents granted prior to 1866; but at increased cost, as the specifications, not being printed, must be copied by hand.

Canadian Patents may now be obtained by the inventors for any of the inventions named in the foregoing list, at a cost of $40 each. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.

Advertisements.

Inside Page, each insertion - - - 75 cents a line.
Back Page, each insertion - - - $1.00 a line.
(About eight words to a line.)

Engravings may head advertisements at the same rate per line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

J. A. FAY & CO.
Cincinnati, Ohio, U.S.A.
WOOD WORKING MACHINERY
Embracing nearly 300 different foots for Arsenals, Navy Yards, Car Shops, Bridge Works, Saw and Planing Mills, Door, Sash, Furniture, Piano & Organ factories &c. including Sawing, Planing, Molding, Mortising, Tenoning, Shaping, Polishing, &c. of the highest standard of excellence and warranted the most labor saving of any in use.
W. H. Doane, President. D. L. Eyon, Secy.

Woodworking Machinery.
For Planing Mills, Furniture and Chair Factories, Car and Agricultural Works, Carriage and Buggy Shops, and General Wood Workers. Manufactured by The Egan Company, Cincinnati, O., U. S. A.
Full assortment of Perin Saw Blades.

CATALOGUES FREE TO ANY ADDRESS
TOOLS OF ALL KINDS
GOODNOW & WIGHTMAN BOSTON

FRICTION CLUTCH
Pulleys and Cut-off Couplings.
JAS. HUNTER & SON, North Adams, Mass.

Leffel Water Wheels,
With Important Improvements.
11,000 IN SUCCESSFUL OPERATION.
FINE NEW PAMPHLET FOR 1883
Sent free to those interested.
JAMES LEFFEL & CO.,
Springfield, Ohio.
110 Liberty St., N. Y. City.



THERMOMETERS.
STANDARD THERMOMETER CO.,
PEABODY, MASS.
FOR SALE BY THE TRADE.

A NEW IDEA! On receipt of $1.00 will send postpaid: A pair of "Hyatt's Pat. Indicators" showing Trump, Points and Games: A fine Pack of Cards and a pocket edition on Whist by Wm. Pole, F. R. S.
What's Trumps?
Prices for single Indicators, sent by mail, 15 cts., 25c. and $1.00.
GEO. W. HYATT,
112 Nassau St., NEW YORK CITY.

PATENTS NEGOTIATED ABROAD.
THE AMERICAN AND FOREIGN INDUSTRIAL ASSOCIATION of New York undertakes the sale of Patents in Europe. Is connected with the "Joint Stock Association" of London, and has Agents in Paris, Brussels and Berlin. For further particulars, address HENRY A. HERBERT, President, 155 Temple Court, New York.

TIGHT & SLACK BARREL MACHINERY
A SPECIALTY
JOHN GREENWOOD & CO.
ROCHESTER N.Y.



THE BEST STEAM PUMP.
Van Duzen's Patent Steam Pump.
Incomparable in cheapness and efficiency. Needs no care or skill; cannot get out of order; has no moving parts.
A Superior Fire Pump.
Instantaneous and powerful, ever ready. Available, wherever steam pressure can be had, for pumping any kind of liquid (hot, cold, sandy, impure, etc.). We make ten sizes, prices from $7 to $75. Capacities from 100 to 20,000 gallons per hour. State for what purpose wanted and send for Catalogue of "Pumps." Van Duzen & Tift, Cincinnati, O.

PERFECT
NEWSPAPER FILE
The Koch Patent File, for preserving newspapers, magazines, and pamphlets, has been recently improved and price reduced. Subscribers to the SCIENTIFIC AMERICAN and SCIENTIFIC AMERICAN SUPPLEMENT can be supplied for the low price of $1.50 by mail, or $1.25 at the office of this paper. Heavy board sides; inscription "SCIENTIFIC AMERICAN," in gilt. Necessary for every one who wishes to preserve the paper.
Address
MUNN & CO.,
Publishers SCIENTIFIC AMERICAN.

© 1884 SCIENTIFIC AMERICAN, INC

A New and Original American Book on the Manufacture of Leather.

DAVIS'S MANUFACTURE OF LEATHER

JUST READY.

The Manufacture of Leather: being a description of all of the Processes for the Tanning, Tawing, Currying, Finishing, and Dyeing of every kind of Leather; including the various Raw Materials and the Methods for Determining their Values; the Tools, Machines, and all details of importance connected with an intelligent and profitable prosecution of the Art, with special reference to the best American Practice. To which are added Complete Lists of all American Patents for Materials, Processes, Tools, and Machines for Tanning, Currying, etc. By Charles Thomas Davis. Illustrated by 302 engravings and 12 samples of Dyed Leathers. 8vo. 824 pages. Price, $10. Free of postage to any address in the world.

☞ *A large illustrated circular of this book, showing the contents, will be sent free to any one in any part of the world who will furnish his address.*

HENRY CAREY BAIRD & CO.,
810 Walnut Street, Philadelphia, Pa.

The Machinists' & Steam Engineers'

PRACTICAL CALCULATOR.

A Compilation of Useful Rules and Problems, arithmetically solved, together with General Information, Applicable to Shop Tools, Mill Gearing, Pulleys, Shafts, Steam Boilers, and Engines,

EMBRACING

Valuable Tables and Instructions in Screw Cutting, Valve and Link Motion, etc., etc.

BY D. B. DIXON.

Full Morocco, 16mo, Oblong, Pocket Form, $2.00.

D. VAN NOSTRAND, Publisher,
23 Murray and 27 Warren Sts., New York.

*** Copies sent by mail, postpaid, on receipt of price.

THE

POPULAR SCIENCE MONTHLY.

Conducted by E. L. & W. J. YOUMANS.

THE POPULAR SCIENCE MONTHLY for 1885 will continue, as heretofore, to supply its readers with the results of the latest investigation and the most valuable thought in the various departments of scientific inquiry.

The wide range of its discussions includes, among other topics:

The bearing of science upon education.

Questions relating to the prevention of disease and the improvement of sanitary conditions.

Subjects of domestic and social economy, including the introduction of better ways of living, and improved applications in the arts of every kind.

The phenomena and laws of the larger social organizations, with the new standard of ethics, based on scientific principles.

The subjects of personal and household hygiene, medicine, and architecture, as exemplified in the adaptation of public buildings and private houses to the wants of those who use them.

Agriculture and the improvement of food-products.

The study of man, with what appears from time to time in the departments of anthropology and archeology that may throw light upon the development of the race from its primitive conditions.

Whatever of real advance is made in chemistry, geography, astronomy, physiology, psychology, botany, zoology paleontology, geology, or such other department as may have been the field of research, is recorded monthly.

Special attention is also called to the biographies, with portraits, of representative scientific men, in which are recorded their most marked achievements in science, and the general bearing of their work indicated and its value estimated.

Volume XXVI begins with the November number, but subscriptions may begin at any time.

Terms: $5.00 per annum.

Single copy, 50 cents.

D. APPLETON & CO., Publishers,

1, 3, and 5 BOND STREET,

NEW YORK.

Gustav E. Stechert, 766 Broadway, N. Y., Has For Sale:

Annales des Ponts et Chaussees.
Complete Set, 1831-80, partly bound, half morocco, $160.00

Crelle's Journal für Mathematik.
Complete Set, 1826-81, vol. 1-90, bound in half morocco, ... $500.00

Dingler's Polytechnisches Journal.
Complete Set, 1820-81. 244 vols. Bound half morocco, ... $250.00

Memoires et Comptes Rendus de la Societé des Ingénieurs Civils.
Complete Set, 1849-79. Cloth, with gilt title, . $85.00

Proceedings of the Institution of Mechanical Engineers.
Complete Set, 1847-83, & Register. Half calf, neat, $175.00

Transactions, Philosophical, of the Royal Society of London.
1665-1800, Abridged, } 110 vols., bound half calf and
1801-81, Complete. } cloth, . . . $575.00

SAVE MONEY

GRAND HOLIDAY CATALOGUE

BY SENDING FOR A COPY OF OUR before buying your Christmas Presents. Whether for young or old, nothing is so sure to please as a handsome book, and our catalogue places an almost endless variety before you to select from at *from 30 to 50 per cent. below the regular retail prices.* We will send a copy by mail FREE to any address. ESTES & LAURIAT, 301-305 Washington St., opp. "Old South," Boston, Mass.

You need the Best Family, Religious, and Literary Weekly Newspaper.

THE INDEPENDENT, New York.

The Pell Mall Gazette, of London, says it is "One of the ablest weeklies in existence."

$3 per year; $5 for two years.

"TRIAL TRIP," 30 cents for a month. Send card for Free Sample Copy. Address

THE INDEPENDENT, New York City.

A. A. GRIFFING IRON CO
STEAM HEATING Apparatus
SOLE MANUFACTURERS
BUNDY STEAM RADIATOR
750 COMMUNIPAW AVE.
JERSEY CITY, N.J.

See Illus. article in SCIENTIFIC AMERICAN Sept. 13, 1884.

JUST OUT.

On receipt of 10 cents, I will send this graceful Bracket Design (size 14 x 15 in.) and my **new Illustrated Catalogue of Scroll Saws and Material, Designs, Novelties, Games, Books, Dog and Cat Collars, Athletic Goods, etc., etc.** Or I will send my complete Catalogue for two 2-cent stamps.

Best Premium offers ever made.

E. H. MOODY,
243 Main St., Hartford, Conn.

Please state where you saw advertisement.



OTTO GAS ENGINE OVER 10,000 IN USE

WORKS WITHOUT ENGINEER OR BOILER. STEAM COAL OR ASH. STARTS AT ONCE AND IS FREE OF DANGER FIRE OR EXPLOSION. 1 to 25 HORSE POWER. SCHLEICHER SCHUMM & CO
47 DEY ST. NEW YORK. 214 RANDOLPH ST CHICAGO. 33d & WALNUT STS PHILADELPHIA



NEW YORK BELTING & PACKING CO.

The Oldest and Largest Manufacturers of the Original

SOLID VULCANITE

Emery Wheels.

All other kinds Imitations and Inferior. Our name is stamped in full upon all our standard **BELTING, PACKING, and HOSE.** Address

JOHN H. CHEEVER, Treas. JOHN D. CHEEVER, Treas'y Dep. **New York Belting and Packing Co., Warehouse, 15 Park Row, opp. Astor House, N. Y.**

Branches: 308 Chestnut Street. Phila., 151 Lake Street, Chicago, and 52 and 54 Summer Street, Boston.



ROCK BREAKERS AND ORE CRUSHERS.

We manufacture and supply at short notice and lowest rates, Stone and Ore Crushers containing the invention described in Letters Patent. issued to Eli W. Blake, June 15th. 1858, together with NEW AND VALUABLE IMPROVEMENTS, for which Letters Patent were granted May 11th and July 20th, 1880. to Mr. S. L. Marsden All Crushers supplied by us are constructed under the superintendence of Mr. Marsden, who, for the past fifteen years, has been connected with the manufacture of Blake Crushers in this country and England.

FARREL FOUNDRY AND MACHINE CO., Manufrs., Ansonia, Conn.
COPELAND & BACON, Agents, New York.

Holland's Double Globe Valves

SOLD BY THE POUND.

They combine the brass seat and rubber disks. We guarantee them to weigh more than any others in the market. Samples sent for trial.

HOLLAND & THOMPSON, Manufacturers,
217 RIVER ST., TROY, N. Y.

FREE HOLIDAY PACKAGE.

To introduce our goods and secure future trade, we will send you (free of charge) if you will send 20 cts. in stamps for postage, &c., 5 pretty Christmas Cards, 5 nice New Year Cards, 5 lovely Birthday Cards a beautiful Gilt Bound Floral Autograph Album illustrated with birds, flowers, ferns, &c., a handsome Photographic Album of all the Presidents of the U.S. with autograph signature of each, also our new illustrated holiday book. U. S. MFG. CO., Hartford, Conn.

RIPON CATHEDRAL. — FULL PAGE illustration and brief description of this ancient English ecclesiastical structure. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **335.** Price 10 cents. To be had at this office and from all newsdealers.



40 CARDS,

"EMBOSSED BEAUTIES,"

Chromos, with your name, 10c., 10 packs for a dollar bill, and a beautiful imported **Velvet Purse** lined with French kid, **Free.** Agents' New Sample Book, Premium List and Price List **Free. U. S. Card Co.,** Centerbrook, Conn.

American Meteorological Journal.

Devoted to Scientific Meteorology, Climatology, etc., etc. Edited by Prof. M. W. Harrington, of Mich. University. Published by W. H. BURR & Co., Detroit, Mich. Subscription, $5.00 per annum.

DO YOU WISH

to possess a knowledge of every kind of Business under the sun? If so, send **15 cents** (silver) to **the International Address and Advertising Bureau, Toronto, Canada,** and have your name printed on our **New List of Classified Addresses for Business Men,** which may be the means of your getting into a good paying business.

Give Name, Address, and usual Occupation.

FREE Silks for Patchwork.

Any lady sending **14** 2c. stamps for three months subscription to the Home Guest, our Popular Literary Magazine, we will present free 1 package beautiful assorted Silk Blocks for patchwork, 1 package Embroidery Silk, assorted colors, 1 lovely Pongee Silk Handkerchief, size 20 x 20, and 1 Book of Fancy Work, new stitches, designs, &c. **THE B. L. SPENCER CO., HARTFORD, CONN.**

WATCHMAKERS.

Before buying, see the Whitcomb Lathe and the Webster Foot Wheel, made by the AMERICAN WATCH TOOL CO., Waltham, Mass. CATALOGUES FREE.



THE CAMERON STEAM PUMP.

STANDARD OF EXCELLENCE.

30,000 IN USE.

MANUFACTURED SOLELY BY

The A. S. CAMERON STEAM PUMP WORKS, Foot East 23d St., New York.

THE PUSEY & JONES COMPANY

WILMINGTON, DELAWARE.

Builders of all description of machinery used by manufacturers of Paper.

THE HARDEN STAR HAND GRENADE FIRE EXTINGUISHER

Puts Out Fire Instantly.

See editorial notice in SCIENTIFIC AMERICAN of November 22d, 1884.

Send for circulars. Address

Harden Hand Grenade Fire Extinguisher Co.,

205 Wabash Ave., Chicago,
10 Oliver St., Boston, or
95 West Broadway, New York.

OPTICAL GOODS

Microscopes, Telescopes, Field and Opera Glasses, Magic Lanterns, etc.; also, Barometers, Thermometers, Compasses, Batteries, Drawing, Drainage, Dairy, and other **Scientific Instruments.** 192-*pp. Catalogue free.*
PRENTICE & SON, Mfg Opticians, **176 B'way, NY.**

SCIENTIFIC AMERICAN SUPPLEMENT. Any desired back number of the SCIENTIFIC AMERICAN SUPPLEMENT can be had at this office for 10 cents. Also to be had of newsdealers in all parts of the country.

PATENTS.

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine Improvements, and to act as Solicitors of Patents for Inventors.

In this line of business they have had *thirty-eight years' experience,* and now have *unequaled facilities* for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reissues, Assignments, and Reports on Infringements of Patents. All business intrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reissues, Infringements, Assignments, Rejected Cases, Hints on the Sale of Patents, etc.

We also send, *free of charge,* a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.

MUNN & CO., Solicitors of Patents,
361 Broadway, New York.

BRANCH OFFICE.—Corner of F and 7th Streets, Washington, D. C.



SHIPMAN STEAM ENGINE.

A BOAT AND STATIONARY ENGINE.

No skilled attendant required! Safe from fire and explosion! No expense when engine stops!

—Steam in FIVE minutes.—

Runs ten hours on less than 3 Gallons of Kerosene. See illustrated article in this paper, September 13.

SHIPMAN ENGINE CO. 55 Franklin St., Boston

PRICES

Including crating, and free delivery on cars or to express company's office from any one of our agencies or factories.

ENGINE No. 1, ½ to ½ H.P...$100
" No. 2, full 1 H.P.... 125
" No. 3, full 2 H.P.... 175

Illustrated Catalogues on receipt of stamp.



BARNES'

Patent Foot and Steam Power Machinery. Complete outfits for Actual Workshop Business. Lathes for Wood or Metal Circular Saws, Scrool Saws, Formers, Mortisers. Tenoners, etc., etc. Machines on trial if desired. Descriptive Catalogue and Price List Free. **W. F. & JOHN BARNES, No. 1999 Main St., Rockford. Ill.**

THE CORINTH CANAL.—A DESCRIPTION of the project of Mr. B. Gerster, engineer in chief of the International Corinth Canal Company, and a sketch of the progress thus far accomplished. Nature of the Isthmus of Corinth. Former undertakings. Route selected by Mr. Gerster. Mode of excavating. Apparatus employed. Illustrated with 6 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **425.** Price 10 cents. To be had at this office and from all newsdealers.



SEBASTIAN, MAY & CO.'S. IMPROVED 160

Screw Cutting Lathe.

Designed for actual work; no toy. Lathes for wood or metal. Drill Presses, Chucks, Drills, Dogs, and machinists' and amateurs' outfits. *Lathes on trial.*

Catalogues mailed on application.

185 & 187 W. Pearl St., Cincinnati, Ohio.

The New Catalogue of Valuable Papers

contained in SCIENTIFIC AMERICAN SUPPLEMENT, sent *free of charge* to any address.

MUNN & CO., 361 Broadway, N. Y.

HOW TO COLOR LANTERN TRANSPARENCIES.—A valuable paper by T. J. Houston giving full directions for the preparation of photographic transparencies, and for painting them. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. **423.** Price 10 cents. To be had at this office and from all newsdealers. The same number contains an illustrated paper on Improvements in Photo-block Printing.—Another valuable paper on the Preparation on Lantern Transparencies is contained in SUPPEMENT, No. **424.**

ROOT'S NEW IRON BLOWER

POSITIVE BLAST.

IRON REVOLVERS, PERFECTLY BALANCED,

Has Fewer Parts than any other Blower.

P. H. & F. M. ROOTS, Manufacturers,
CONNERSVILLE, IND.

S. S. TOWNSEND, Gen. Agt., 22 Cortland St., 9 Dey St., COOKE & CO., Selling Agts., 22 Cortland Street, JAS. BEGGS & CO., Selling Agts. 9 Dey Street,

NEW YORK.

SEND FOR PRICED CATALOGUE.

"CHAMPION" "6-LEVER" RIM NIGHT LATCHES. See illustration in SCI. AM., Nov. 29, 1884. Each is packed separately, with three nickel plated steel keys, and complete trimmings. *Sample,* with *bronze escutcheon,* mailed for *introduction,* on receipt of $ 20. Full *nickel plated* sample for $2.60. Add 10 cents for *registering* the package. Order direct, or through any responsible dealer. Send 2c. stamp for *Illustrated List* of *Latches, Locks, Padlocks, etc. Miller Lock Co., Philadelphia, Pa.*

MALLEABLE

AND FINE GRAY IRON ALSO STEEL CASTINGS FROM SPECIAL PATTERNS FINE TINNING JAPANNING AND FINISHING &c.

THOMAS DEVLIN & CO
LEHIGH AVE. & AMERICAN ST. PHILA.

FRET SAW OR BRACKET WOODS,

IN CHOICE AND RARE VARIETY,
PLANED READY FOR USE.
ALSO LATEST BOOKS OF DESIGNS.
GEO. W. READ & CO.,
Manufacturers Mahogany and other Cabinet Woods.
186 to 200 LEWIS ST., N. Y.

FOUNDRY PRACTICE.

ADVERTISERS wish to produce a Reliable Book on all kinds of Foundry Practice, embodying the results of actual experience in different parts of the world, in Iron —Malleable, Cast, etc.—Steel, Brass, and other work. Persons qualified to contribute practical information—which will be paid for—should address G. H., office of THE IRONMONGER, 42 Cannon Street, London, E. C. The Editor-in-Chief will arrange the purely literary side of the matter, so that those having the requisite knowledge need not hesitate to apply on account of their lack of literary experience. Drawings should be furnished where they can be used advantageously.

SEND FOR LIST OF

FINISHED PULLEYS, at 4 cts. per pound.
ROUGH PULLEYS, at 2 1-2 cts. per pound.
The JOHN T. NOYE MFG. CO., BUFFALO, N. Y.

Syracuse Malleable Iron Works

DYKE'S BEARD ELIXIR Forces luxuriant Mustache, Whiskers, or hairon bald heads in 30 to 90 days. No injury. Easily used. Beats the world. 2 or 3 Pkgs does the work. Will prove it or forfeit $100.00. Price per Package with directions sealed and postpaid 25 cents, 3 for 50 cts., stamps or silver. **L. A. L. SMITH & CO., Agents, Palatine, Ill.**

Nervous Debility Quick permanent cure. Book free. Civiale Agency, 160 Fulton St., N.Y.

OPIUM & WHISKY HABITS

cured with Double Chloride of Gold. We challenge investigation. 10,000 Cures. Books free. The **LESLIE E. KEELEY CO.** DWIGHT, ILL.

FOREIGN PATENTS.

Their Cost Reduced.

The expenses attending the procuring of patents in most foreign countries having been considerably reduced, the obstacle of cost is no longer in the way of a large proportion of our inventors patenting their inventions abroad.

CANADA.—The cost of a patent in Canada is even less than the cost of a United States patent, and the former includes the Provinces of Ontario, Quebec, New Brunswick, Nova Scotia, British Columbia, and Manitoba.

The number of our patentees who avail themselves of the cheap and easy method now offered for obtaining patents in Canada is very large, and is steadily increasing.

ENGLAND.—The new English law, which went into force on Jan. 1st, enables parties to secure patents in Great Britain on very moderate terms. A British patent includes England, Scotland, Wales, Ireland, and the Channel Islands. Great Britain is the acknowledged financial and commercial center of the world, and her goods are sent to every quarter of the globe. A good invention is likely to realize as much for the patentee in England as his United States patent produces for him at home, and the small cost now renders it possible for almost every patentee in this country to secure a patent in Great Britain, where his rights are as well protected as in the United States.

OTHER COUNTRIES.—Patents are also obtained on very reasonable terms in France, Belgium, Germany Austria, Russia, Italy, Spain (the latter includes Cuba and all the other Spanish Colonies), Brazil, British India, Australia, and the other British Colonies

An experience of THIRTY-EIGHT years has enabled the publishers of THE SCIENTIFIC AMERICAN to establish competent and trustworthy agencies in all the principal foreign countries, and it has always been their aim to have the business of their clients promptly and properly done and their interests faithfully guarded.

A pamphlet containing a synopsis of the patent laws of all countries, including the cost for each, and other information useful to persons contemplating the procuring of patents abroad, may be had on application to this office.

MUNN & CO., Editors and Proprietors of THE SCIENTIFIC AMERICAN, cordially invite all persons desiring any information relative to patents, or the registry of trade-marks, in this country or abroad, to call at their offices, 361 Broadway. Examination of inventions, consultation, and advice free. Inquiries by mail promptly answered.

Address, **MUNN & CO.,**
Publishers and Patent Solicitors,
361 Broadway, New York.

Branch Office, cor. F and 7th Streets, opposite Patent Office Washington, D. C.

© 1884 SCIENTIFIC AMERICAN, INC

Advertisements.

Inside Page, each insertion - - - 75 cents a line.
Back Page, each insertion - - - $1.00 a line.

(About eight words to a line.)

Engravings may head advertisements at the same rate per line, by measurement, as the letter press. Advertisements must be received at publicatio office as early as Thursday morning to appear in ext issue.

Pratt's Multiform Screw Driver.



Twelve screw drivers in one. The points as seen in the cut are of various widths and thicknesses to fit all size screws. They are held in the stock by a screw. This screw may be turned by one of the points held in the fingers. These points operate much better than an ordinary driver, as they are not ground to a bevel.

The bit can readily be taken out of the handle and used in a bit brace.

Handle, polished rosewood.....7 inches long.
Bit ⅜ round steel.....7 inches long.

It is the most useful and beautiful screw driver which was ever put on the market. Price by mail, prepaid, $1. Hardware dealers will furnish it at same price.

MILLERS FALLS CO.,
74 Chambers St., New York.

VOLNEY W. MASON & CO.,
FRICTION PULLEYS CLUTCHES and ELEVATORS.
PROVIDENCE, R. I.

TELEPHONES.

The United States Telephone Mfg Co.

This Company is the owner of the patents of James W. McDonough for speaking telephones.

Mr. McDonough's application for patent was the first that was made in the U. S. Patent office for a speaking telephone; all other telephones are an infringement of these patents. This Company also owns patents covering a complete system of telephone exchanges.

All telephones obtained except from this Company or its authorized licensees are infringements, and the makers, sellers, and users will be proceeded against.

This Company are now prepared to sell Telephones of the most improved form.

For particulars apply to

The United States Telephone Manufacturing Co.,
187 BROADWAY N. Y.

DRAWING INSTRUMENTS.

Illustrated catalogue sent on application to
WM. T. COMSTOCK,
6 Astor Place,
New York.



F. Brown's Patent
FRICTION CLUTCH.

Send for Illustrated Catalogue and Discount Sheet to

A. & F. BROWN, 43 Park Place, New York.

SHAFTS PULLEYS HANGERS

The "MONITOR."

A NEW LIFTING AND NON-LIFTING INJECTOR.



Best Boiler Feeder in the world. Greatest Range yet obtained. Does not Break under Sudden Changes of Steam Pressure.

Also Patent
EJECTORS
OR
Water Elevators,
For Conveying Water and Liquid.
Patent Oilers, Lubricators, etc.

NATHAN MANUFACTURING COMPANY,
Send for catalogue. **92 & 94 Liberty St., New York.**



WITHERBY, RUGG & RICHARDSON, Manufacturers of Patent Wood Working Machinery of every description. Facilities unsurpassed. Shop formerly occupied by R. Bail & Co., Worcester, Mass. Send for Catalogue.

H.W.JOHNS' ASBESTOS LIQUID PAINTS ROOFING.

Fire-proof Building Felt,

Steam Pipe and Boiler Coverings, Steam Packing, Mill Board, Gaskets, Sheathings, Fire-proof Coatings, Cement, &c.

DESCRIPTIVE PRICE LIST AND SAMPLES FREE.

H. W. JOHNS M'F'G CO.,
87 Maiden Lane, New York.
170 N. 4th St., Phila. 45 Franklin St., Chicago.

MAGIC LANTERN ELECTRIC LIGHT Steady, fixed-focus, Iridium, Arc Lamp. Also
LIME LIGHT MADE EASY!
Cheapest, Safest, Best. *Send for recent circular.*
MAGIC LANTERNS AND FINE SLIDES a Specialty. L. J. MAROY, 1340 Chestnut St., Phila.



BURNHAM'S SELF-ADJUSTING SWING CHECK VALVE.

Users of Check Valves will please note the advantage these Valves possess over all others. The most important claim is, that as the **Jenkins' Disk wears, the yoke** [illegible] **passes around the seat moves away from the seat in proportion to the wear of the Disk, thus causing a uniform wear of** [illegible] **until said Disk is completely worn out.**

JENKINS BROS.,
71 John Street, New York. Send for Price List "A." 79 Kilby St., Boston.

AGENTS:

Rees, Shook & Co., Pittsburg, Pa.
Gibson & Clark, Cincinnati, Ohio.
Chafer & Becker, Cleveland, Ohio.
Dunham, Carrigan & Co., San [illegible]
Ahrens [illegible], Louisville, Ky.
James [illegible], Detroit, Mich.
Weir [illegible]go, Ill.
Weir & Craig, Minneapolis, Minn.
Pond Engineering Co., St. Louis, Mo.
Marinette Iron Wks. Co., Chicago, Ill.
English Brothers, Kansas City, Mo.
He [illegible]ff M'f'g Co., Denver, Col.

American Bell Tele. Co. Patent Drawer 2 Boston Mass. 1884

GEO. W. FIFIELD,
MANUFACTURER OF ENGINE LATHES FROM 16" TO 48" SWING
CUTS, PHOTOGRAPHS AND PRICES FURNISHED ON APPLICATION.
LOWELL, MASS., U.S.A.

MAGIC LANTERNS

And **STEREOPTICONS**, all prices. Views illustrating every subject for **PUBLIC EXHIBITIONS**, etc.
☞ *A profitable business for a man with a small capital.* Also, Lanterns for Home Amusement. 136 page Catalogue *free.*
McALLISTER, Mfg. Optician, **49 Nassau St., N. Y.**

PHOTOGRAPHIC OUTFITS for Amateurs. *Opera Glasses Microscopes, Telescopes, Spectacles, Barometers, Thermometers.* **W. H. WALMSLEY & CO.** successors to R. & J. Beck, Philada. Illus. Price List free to any address.

SUPPLY DEPOT
FOR
AMATEUR AND Professional Mechanics.

Foot Lathes, Scroll Saws, Carving, Engraving and **Repousse** Tools, Chucks, Drills, Nippers, Pliers, Saw Blades, Designs, Fancy Woods, &c, &c. Shipman **Engines** for light machinery, ⅛, 1 and 2 H. P.

Send 15 cents for 128 page Catalogue. Price paid for it can be deducted from first purchase amounting to $2.

SCROLL SAWS From $2.00 to $25. **J. J. WATROUS**, 213 Race, St., **CINCINNATI, OHIO.**

SPEAKING TELEPHONES.

THE AMERICAN BELL TELEPHONE COMPANY,

W. H. FORBES, *President.* W. R. DRIVER, *Treasurer.* THEO. N. VAIL, *Gen. Manager.*

Alexander Graham Bell's patent of March 7, 1876, owned by this company, covers every form of apparatus, including Microphones or Carbon Telephones, in which the voice of the speaker causes electric undulations corresponding to the words spoken, and which articulations produce similar articulate sounds at the receiver. The Commissioner of Patents and the U. S. Circuit Court have decided this to be the true meaning of his claim; the validity of the patent has been sustained in the Circuit on final hearing in a contested case, and many injunctions and final decrees have been obtained on them.

This company also owns and controls all the other telephonic inventions of Bell, Edison, Berliner, Gray, Blake, Phelps, Watson, and others.

(Descriptive catalogues forwarded on application.)

Telephones for Private Line, Club, and Social systems can be procured directly or through the authorized agents of the company.

All telephones obtained except from this company, or its authorized licensees, are infringements, and the makers, sellers, and users will be proceeded against.

Information furnished upon application.

Address all communications to the
AMERICAN BELL TELEPHONE COMPANY,
95 Milk Street, Boston, Mass.

WATER.

Cities, Towns, and Manufactories

Supplied by GREEN & SHAW

PATENT TUBE AND GANG WELL SYSTEM.

Wm. D. Andrews & Bro., 233 Broadway, N. Y.

Infringers of above patents will be prosecuted.

THE PAYNE AUTOMATIC ENGINE

Gives more power from same amount of fuel and water than any engine



made, and 50 per cent more power than rated at. All engines warranted. All sizes and styles, 2 to 250 horse power. Send for prices and catalogue A 4.

B. W. PAYNE & SONS,
P. O. Box 1207. Elmira, N. Y.

CARY & MOEN STEEL WIRE OF EVERY DESCRIPTION & STEEL SPRINGS. 234 W. 29. ST. NEW YORK CITY

EVAPORATING FRUIT

Full treatise on improved methods, yields, profits, prices and general statistics, **FREE.**

AMERICAN MAN'F'G CO.
"BOX R," WAYNESBORO, PA.

Steel Castings

From ¼ to 15,000 lb. weight, true to pattern, of unequaled strength, toughness, and durability. 20,000 Crank Shafts and 15,000 Gear Wheels of this steel now running prove its superiority over other Steel Castings. Send for circular and price list.

CHESTER STEEL CASTINGS CO.,
407 Library St., Philadelphia, Pa.

Rider's New and Improved
COMPRESSION
Hot Air Pumping Engine

New and Improved Designs.
INTERCHANGEABLE PLAN
MANUFACTURED BY
DELAMATER IRON WORKS,
C. H. DELAMATER & CO., Proprietors,
No. 16 CORTLANDT ST., NEW YORK, N. Y.
And 40 Dearborn Street Chicago, Ill.

COLUMBIA BICYCLES AND TRICYCLES.

New Illustrated (36 page) Catalogue, giving full description of these machines, sent for stamp.

THE POPE M'F'G CO.,
597 Washington St., Boston, Mass.

THE TELEREMA
A SATISFACTORY SUBSTITUTE FOR THE TELEPHONE
SEND FOR CIRCULAR
H. E. HUSTON
Monticello Ill.

Pietsch Self-Ventilating Sewer Trap. Highest award of the American Institute. In operation at the office of SCIENTIFIC AMERICAN.
HERMAN PIETSCH, Flatbush, L. I.

PRINTERS' ROLLERS. BEST AND CHEAPEST.
Used in printing the SCIENTIFIC AMERICAN.
D. J. Reilly & Co., 326 Pearl St., New York City.

40 **Hidden Name, Embossed and New Chromo Cards,** name in new type, **an Elegant 48page Gilt bound Floral Autograph Album** with quotations, **12 page Illustrated Premium** and Price List and Agent's Canvassing Outfit all for 15c. SNOW & CO., Meriden, Conn.

PLAYS, Dialogues, Tableaux, Speakers, etc., for School, Club, and Parlor. Best out. Catalogue H free. T. S. DENISON, Chicago, Ill.



NATIONAL TOOL CO.,
MANUFACTURERS OF
MACHINISTS TOOLS.
WILLIAMSPORT, PA.
PLANERS A SPECIALTY.

The Seibert Cylinder Oil Cup Co.,



Manufacturers of **Oil Cups for Locomotive, Marine, and Stationary Engine Cylinders, under the Seibert and Gates Patents, with Sight Feed.**

TAKE NOTICE.

The "Sight Feed" is owned exclusively by this Company. See Judge Lowell's decision in the United States Circuit Court, District of Massachusetts, Feb. 23, '82. All parties, except those duly licensed by us, are hereby notified to desist the use, manufacture, or sale of infringing Cups, as we shall vigorously pursue all infringers.

The Seibert Cylinder Oil Cup Co.
53 Oliver Street, Boston, Mass.

PATENT COLD ROLLED SHAFTING.

The fact that this shafting has 75 per cent. greater strength, a finer finish, and is truer to gauge, than any other in use renders it undoubtedly the most economical. We are also the sole manufacturers of the CELEBRATED COLLINS' PAT. COUPLING, and furnish Pulleys, Hangers, etc., of the most approved styles. Price list mailed on application to JONES & LAUGHLINS, Limited, Try Street, 2d and 3d Avenues, Pittsburg, Pa.
Corner Lake and Canal Sts., Chicago, Ill.
☞ Stocks of this shafting in store and for sale by FULLER, DANA & FITZ, Boston, Mass.
Geo. Place Machinery Agency, 121 Chambers St., N. Y.

A CHRISTMAS GIFT.

Every Christmas we make the little folks a Christmas present. This year we have something nice and pretty. To introduce our goods in every home we will send to any boy or girl **free** of charge, if you will send 20c. for postage, &c., **3 Pretty Dolls** with beautiful life-like features, one little boy and two girl dolls with a complete wardrobe of 32 pieces, dresses, hats, cloaks, &c., one elegant gilt-bound floral Autograph Album illustrated with birds, ferns, scrolls, &c., 5 lovely Christmas Cards, one pretty Birthday Card and a 50p. Holiday Book. A. L. BABCOCK & CO., Centerbrook, Conn.

COE BRASS MFG. CO. TORRINGTON — CONN. BRASS WIRE COPPER MATERIAL FOR METALLIC AMMUNITION IN SHEETS A SPECIALTY AND BLANKS

FOOT LATHES

The best for Amateur, Electrician, and Work Shop use.
Swing 8x18 ins. Improved foot power, tool carriage, slide rest, set over tail stock, etc. Complete, $35.00.
Foot Power Circular Saw.

NARRAGANSETT MACHINE CO.,
Send Stamp for Catalogue. Providence, R. I.

GASKILL'S STEAM PUMPS,
AND
GASKILL'S HIGH DUTY PUMPING ENGINES.
For public water supply. Manufactured by
THE HOLLY MFG. CO., Lockport, N. Y.

KORTING UNIVERSAL INJECTOR



DOUBLE TUBE.
ALL BRASS
FOR BOILER FEEDING.
Operated by one handle.
WILL LIFT HOT WATER.
POSITIVE ACTION GUARANTEED UNDER ALL CONDITIONS.
NO ADJUSTMENT FOR VARYING STEAM PRESSURE.
WILL LIFT WATER 25 FEET. SEND FOR DESCRIPTIVE CIRCULAR.

OFFICES AND WAREROOMS:

Philada., 12th & Thompson Sts.
Boston, 61 Oliver St.
Augusta, Ga., 1026 Fenwick St.
San Francisco, Cal., 2 California Street.
New York, 109 Liberty Street.
Denver, Col., 438 Blake Street.
Chicago, Ill., 204 Lake St.

$5 to $20 per day at home. Samples worth $5 free. Address STINSON & Co., Portland, Maine.

HARTFORD STEAM BOILER INSPECTION AND INSURANCE CO. HARTFORD. CONN.

HALL & SONS BUFFALO N.Y. SPRAY FEED WATER PURIFIER FOR STEAM BOILERS U.S. & FOREIGN PATENTS

WM. A. HARRIS,
Providence, R. I. (Park St.), Six minutes' walk West from station.
Original and Only Builder of the
HARRIS-CORLISS ENGINE,
With Harris Pat. Improvements, from 10 to 1,000 H. P.
Send for copy Engineer's and Steam User's Manual. By J. W. Hill M.E. Price $1.25.

The Scientific American.

THE MOST POPULAR SCIENTIFIC PAPER IN THE WORLD.

Published Weekly, $3.20 a Year; $1.60 Six Months.

☞ This unrivaled periodical, now in its **fortieth year,** continues to maintain its high reputation for excellence, and enjoys the largest circulation ever attained by any scientific publication.

Every number contains sixteen large pages, beautifully printed, elegantly illustrated; it presents in popular style a descriptive record of the most novel, interesting, and important advances in Science, Arts, and Manufactures. It shows the progress of the World in respect to New Discoveries and Improvements, embracing Machinery, Mechanical Works, Engineering in all branches, Chemistry, Metallurgy, Electricity, Light, Heat, Architecture, Domestic Economy, Agriculture, Natural History, etc. It abounds with fresh and interesting subjects for discussion, thought, or experiment; furnishes hundreds of useful suggestions for business. It promotes Industry, Progress, Thrift, and Intelligence in every community where it circulates.

The SCIENTIFIC AMERICAN should have a place in every Dwelling, Shop, Office, School, or Library. Workmen, Foremen, Engineers, Superintendents, Directors, Presidents, Officials, Merchants, Farmers, Teachers, Lawyers, Physicians, Clergymen, people in every walk and profession in life, will derive benefit from a regular reading of THE SCIENTIFIC AMERICAN.

Terms for the United States and Canada, $3.20 a year; $1.60 six months. Specimen copies free. Remit by Postal Order or Check.

MUNN & CO., Publishers,
361 Broadway, New York.

THE Scientific American Supplement.

THE SCIENTIFIC AMERICAN SUPPLEMENT is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archæology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information pertaining to these and allied subjects is given, the whole profusely illustrated with engravings.

The most important Engineering Works, Mechanisms and Manufactures at home and abroad are represented and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, $5.00 a year, or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for $7.00. Address and remit by postal order or check,

MUNN & Co., 361 Broadway, N. Y.,
Publishers SCIENTIFIC AMERICAN.

To Foreign Subscribers.—Under the facilities of the Postal Union, the SCIENTIFIC AMERICAN is now sent by post direct from New York, with regularity, to subscribers in Great Britain, India, Australia, and all other British colonies; to France, Austria, Belgium, Germany, Russia, and all other European States; Japan, Brazil, Mexico, and all States of Central and South America. Terms, when sent to foreign countries, Canada excepted, $4, gold, for SCIENTIFIC AMERICAN, one year; $9, gold, for both SCIENTIFIC AMERICAN and SUPPLEMENT for one year. This includes postage, which we pay. Remit by postal order or draft to order of

MUNN & CO., 361 Broadway, New York.

PRINTING INKS.

THE "Scientific American" is printed with CHAS. ENEU JOHNSON & CO.'S INK. Tenth and Lombard Sts. Phila., and 47 Rose St., opp. Duane St., N. Y

© 1884 SCIENTIFIC AMERICAN, INC